

To: 1 120588
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

7-9
API NUMBER 15-185-21,926-0000 137

NE SE NW, SEC. 31, T. 24 S, R. 11 W/E
3630 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 9247
Operator: Cincris Energy
Name & Address 2213 31st
Great Bend, KS 67530

Lease Name Newell Well # 1
County Stafford 133.96
Well Total Depth 4122 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 266

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____
Plugging Contractor Rockhold Engineering, Inc. License Number 5111
Address P.O. Box 698, Great Bend, KS 67530

Company to plug at: Hour: 10:30 a.m. Day: 9 Month: 7 Year: 1991

Plugging proposal received from Jim Rockhold
(company name) Rockhold Engineering, Inc. (phone) 316-792-2506

were: 5 1/2" at 3962' w/125 sx cement, PBTB 3919', Perfs at 3637-39'
1st plug sand back to 3580' and dump 5 sx cement on top of sand through bailer,
2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 100 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:15 p.m. Day: 9 Month: 7 Year: 1991

ACTUAL PLUGGING REPORT 1st plug sanded back to 3580' and dumped 5 sx cement on top of sand
through bailer,
2nd plug pumped in 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement,
10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.
Pumping pressure 0-700 psi and shut in 400 psi.

RECEIVED
STATE CORPORATION COMMISSION

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3041' of 5 1/2" casing. JUL 17 1991

INVOICED (if additional description is necessary, use BACK of this form.) CONSERVATION DIVISION
I (did / did not) observe this plugging. Wichita, Kansas

DATE 7-22-91
INV. NO. 32356

Signed Duane Rankin
(TECHNICIAN)