

To: 1 120589  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 9247  
Operator: Cincris Energy  
Name & Address 2213 31st  
Great Bend, KS 67530

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Rockhold Engineering, Inc. License Number 5111

Address P.O. Box 698, Great Bend, KS 67530

Company to plug at: Hour: 9 a.m. Day: 9 Month: 7 Year: 19 91

Plugging proposal received from Jim Rockhold

(company name) Rockhold Engineering, Inc. (phone) 316-792-2506

were: 5 1/2" at 3909' w/150 sx cement, Perfs at 3550-55'

1st plug sand back to 3500' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 100 sx cement.

Plugging Proposal Received by Richard Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 10:30 a.m. Day: 9 Month: 7 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug sanded back to 3500' and dumped 5 sx cement on top of  
sand through bailer,

2nd plug pumped in 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement,

10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement

Pumping pressure 0-600 psi and shut in 300 psi.

RECEIVED  
STATE CORPORATION COMMISSION  
7-17-91  
JUL 17 1991

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2965' of 5 1/2" casing.

(If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

**INVOICED**

DATE 7-22-91

INV. NO. 32357

Signed Duan Runkin  
(TECHNICIAN)

7-9  
API NUMBER 15-185-22,245-0000  
SW SE NW, SEC. 31, T. 24 S, R. 11 W/E  
2970 feet from S section line  
3630 feet from E section line  
Lease Name Newell Well # 2  
County Stafford 127.07  
Well Total Depth 3910 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 252