

1 120912

3-29

15-185-00809-00-01

API NUMBER 15- Docket #D-23,644

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

NW SW NE, SEC. 31, T. 24 S, R. 11  
3630 feet from S section 11-  
2310 feet from E section 11-

TECHNICIAN'S PLUGGING REPORT

Operator License # 9247  
Operator: Cincris Energy Company  
Name:  
Address: 22996 El Toro Rd.  
El Toro, CA 92630

Lease Name: Irvine Well # 1  
County: Stafford  
Well Total Depth: 4400 143.00 ft  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 308

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ X O&A  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor: Kelso Casing Pulling, Inc. License Number 6050

Address: P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 10 a.m. Day: 29 Month: 3 Year: 19 94

Plugging proposal received from: Mike Kelso

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

Work: 5 1/2" at 4154' w/200 sx cement, Open hole 4154-4400'

1st plug sand back to 4100' and dump 5 sx cement on top of sand through bailer.

2nd plug pump in 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release 8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Case Morris (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11:15 a.m. Day: 29 Month: 3 Year: 1994

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 4100' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Pumping pressure 0-250 psi and shut in 100 psi.

RECEIVED STATE CORPORATION COMMISSION

4-1-94

APR 01 1994

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2200' of 5 1/2" casing.

(if additional description is necessary, use BACK of CONSERVATION DIVISION Wichita, Kansas

INVOICED

DATE APR 08 1994

INV. NO. 40274

3-29

Signed: [Signature] (TECHNICIAN)