

To: 1 040408  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 3911

Operator: Rama Operating Co., Inc.  
Name & Address: P.O. Box 159  
Stafford, KS. 67578

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS. 67524

Company to plug at: Hour: 11:30 am Day: 22 Month: 3 Year: 19 90

Plugging proposal received from Milard Kelso

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: 7" at 3833' PRTD = 3780' Perfs. at 3609-3613' and 3581'-3584'

1<sup>st</sup> plug - sand back to 3530' and dump 7 sx. cement on top of sand through bailer,

2<sup>nd</sup> plug - pump 400<sup>#</sup> hulls, 10 sx. gel, 50 sx. cement, 10 sx. gel, - release 10<sup>3/4</sup>" wiper plug and pump 125 sx. cement.

Plugging Proposal Received by Mike Wilson (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 12:15 p.m. Day: 22 Month: 3 Year: 19 90

ACTUAL PLUGGING REPORT 1<sup>st</sup> plug - sanded back to 3530' and dumped 7 sx. cement on top of sand through bailer,

2<sup>nd</sup> plug - pumped 300<sup>#</sup> hulls, 10 sx. gel, 50 sx. cement, 10 sx. gel, 100<sup>#</sup> hulls, and pumped 125 sx. cement.

Maximum Pressure 300<sup>#</sup> and shut in 50<sup>#</sup>

Remarks: Used 60/40 pozmix 6<sup>70</sup> gel by Allied. Recovered 16 1/2' of 7" casing  
(if additional description is necessary, use BACK of this form.)

**INVOICED**

DATE 4-6-90

INV. NO. 27806

CONSERVATION DIVISION  
Wichita, Kansas

REC'D  
4-2-90

Signed Stephen J. Puffer (TECHNICIAN)