

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-23125-00-01
Spot: NWSESW Sec/Twnshp/Rge: 11-24S-12W
990 feet from S Section Line, 1650 feet from W Section Line
Lease/Unit Name: STAFFORD WEST Well Number: 1
County: STAFFORD Total Vertical Depth: 3840 feet

Operator License No.: 3911
Op Name: RAMA OPERATING CO., INC.
Address: 101 S. MAIN
STAFFORD, KS 67578

Production Casing Size: 5.5 feet: 3836 WITH 125 SX CMT
Surface Casing Size: 8.625 feet: 296 WITH 200 SX CMT

\$12480

Well Type: EOR UIC Docket No: _____ Date/Time to Plug: 06/24/2003 12:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: SAND TO 3790' & 5 SX CMT. PLUG AT 650' WITH 50 SX CMT. PLUG AT 330' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE DURRANT Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 06/24/2003 1:55 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

PERFS AT 3836-3840'. SAND TO 3750' & 5 SX CMT WITH DUMP BAILER. SPOTTED PLUGS THROUGH CASING WHILE PULLING. 1ST PLUG AT 650' WITH 10 SX GEL -100# HULLS - 50 SX CMT. 2ND PLUG AT 330' WITH 100# HULLS - 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

RECEIVED

7-7-03
JUL 07 2003

KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2620' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

RECEIVED
JUL - 2 2003
KCC Dodge City

Signed Richard W. Lacey
(TECHNICIAN)

[Signature]
PAUL CHERRY