

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 2/89

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-185-22,692 (of this well).
(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR Martin Oil Producers, Inc. OPERATOR'S LICENSE NO. 5907

ADDRESS 150 N. Main, Suite 1010 PHONE # (316) 264-0352

LEASE (FARM) Heyen WELL NO. 2 WELL LOCATION E 7/2 NE 100' W SW COUNTY Stafford

SEC. 10 TWP. 24S RGE. 14 (E) or (W) TOTAL DEPTH 4190 PLUG BACK TD _____

Check One:

OIL WELL _____ GAS WELL _____ D & A SWD or INJ WELL _____ DOCKET NO. _____

SURFACE CASING SIZE 8 5/8 SET AT 301 CEMENTED WITH 200 SACKS

CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

PERFORATED AT _____

CONDITION OF WELL: GOOD POOR _____ CASING LEAK _____ JUNK IN HOLE _____

PROPOSED METHOD OF PLUGGING Fill hole w/heavy mud: 1st plug at 915' w/50 sx; 2nd plug at 330' w/50 sx; 3rd plug at 40' w/10 sx, 15' sx in rathole, 10' sx in mousehole. All cement 60/40 pozmix w/6% gel, 1/4# Floccel per sx.

(If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? yes IS ACO-1 FILED? No
(If not explain.) Sent to operator to complete

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 12:15 p.m. on 7-16-90

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Harvey Moore. PHONE # (316) 995-4955

ADDRESS Box 163, Belpre, KS 67519

PLUGGING CONTRACTOR Abercrombie Drilling, Inc. LICENSE NO. 5422

ADDRESS 150 N. Main, Suite 801, Wichita, KS 67202 PHONE # (316) 262-1841

RECEIVED
Rec'd 7-24-90
JUL 24 1990

CONSERVATION DIVISION
Wichita, Kansas

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

SIGNED: Jack K. Wharton
(Operator or Agent)

DATE: July 20, 1990

ABERCROMBIE DRILLING, INC.

801 UNION CENTER
WICHITA, KANSAS 67202

Martin Oil Producers, Inc.
150 N. Main, Suite 1010
Wichita, KS 67202

Heyen #2
100' W of E/2 NE SW
Sec. 10-24S-14W
Stafford County, Kansas

Contractor: Abercrombie Drilling, Inc.
Surface: 8 5/8"-23# set at 301 w/200 sx

DRILLER'S WELL LOG

7-9-90	0 - 80	Sand
	80 - 110	Clay
	110 - 305	Blue Shale
7-10-90	305 - 582	Shale and Red beds
	582 - 1910	Shale
7-11-90	1910 - 2240	Shale and Lime
	2240 - 2860	Lime and Shale
7-12-90	2860 - 3565	Lime and Shale
7-13-90	3565 - 3960	Lime and Shale
7-14-90	3960 - 4070	Lime and Shale
	4070 - 4090	Lime
7-15-90	4090 - 4180	Lime and Shale
7-16-90	4180 - 4190	Lime and Shale
	4190	Rotary Total Depth

RECEIVED
STATE OFFICE

UL 24 1990

CONSERVATION DIVISION
Wichita, Kansas