

To: 1051706 8-7
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 185-22,922 - 0000
App. SE NE SW, SEC. 9, T. 24 S, R. 13 W/E
1715 feet from S section line
2245 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5097
Operator: Martin Oil Producers, Inc.
Name & Address: 150 N. Main, Ste. 1010
Wichita, KS 67202

Lease Name Holmes Well # 1B
County Stafford 132.92
Well Total Depth 4090 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 307

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X
Other well as hereinafter indicated _____

Plugging Contractor Allen Drilling Company License Number 5418
Address P.O. Box 1389, Great Bend, KS 67530

Company to plug at: Hour: 6 a.m. Day: 7 Month: 8 Year: 19 93

Plugging proposal received from Richard Stevenson
(company name) Allen Drilling Company (phone) 316-793-5681

work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 784-805'
1st plug at Arbuckle +50' with 50 sx cement, 2nd plug at 800' with 50 sx cement,
3rd plug at 330' with 50 sx cement, 4th plug at 40' with 10' sx cement,
5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X
Operations Completed: Hour: 8:30 a.m. Day: 7 Month: 8 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug at 800' with 50 sx cement,
2nd plug at 330' with 50 sx cement,
3rd plug at 40' with 10 sx cement,
4th plug to circulate rathole with 15 sx cement,

8-12-93
RECEIVED
STATE CORPORATION COMMISSION

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.
(If additional description is necessary, use BACK of this form.)

INVOICED

I (did / did not) observe this plugging.

DATE 8-17-93

Signed Richard M. Lacey
(TECHNICIAN)

INV. NO. 38361

EFFECTIVE DATE: 7-24-93 **SKID RIG 2nd Line** FROM MUST BE SIGNED
 DISTRICT # Wichita STATE OF KANSAS NOTICE OF INTENTION TO DRILL ALL BLANKS MUST BE FILLED
 35A7 X Yes No Must be approved by the K.S.C. five (5) days prior to commencing well 185-22-922

Expected Spud Date July 21 1993
 month day year

Sec 9 Twp 24 S. Rg 13 East West

OPERATOR: License # 5097
 Name: Martin Oil Producers, Inc.
 Address: 150 N. Main, #1010
 City/State/Zip: Wichita, KS 67202
 Contact Person: Joe Moreland
 Phone: 316-264-0352

1715 feet from South / North line of Section
2245 feet from East / West line of Section
 IS SECTION Y REGULAR IRREGULAR?
 (NOTE: Locate well on the Section Plat on Reverse Side)
 County: Stafford
 Lease Name: Holmes Well #: 1B
 Field Name: WC

CONTRACTOR: License # 5418
 Name: Allen Drilling Co.
 Well Drilled For: Fax (316) 793-5877
 Well Class: Type Equipment:

Is this a Prorated/Spaced Field? yes X no
 Target Formation(s): Lsg. Arb.
 Nearest lease or unit boundary: 330
 Ground Surface Elevation: 1915 feet
 Water well within one-quarter mile: X
 Public water supply well within one mile: X
 Depth to bottom of fresh water: 100
 Depth to bottom of usable water: 240
 Surface Pipe by Alternate: X 1 2
 Length of Surface Pipe Planned to be set: (275) 260'
 Length of Conductor pipe required: NONE
 Projected Total Depth: 4150
 Formation at Total Depth: Arbuckle
 Water Source for Drilling Operations:
 X well farm pond other:

X. Oil ✓ ... Enh xcc ... Infield X Mud Rotary
 ... Gas ... Storage ... Pool Ext. ... Air Rotary
 ... DUWG ... Disposal X Wildcat ... cable
 ... Seismic; ... # of Holes ... Other
 If NO old well information as follows:
 Operator:
 Well Name:
 Comp. Date: ... Old Total Depth

Directional, Deviated or Horizontal wellbore? no
 If yes, true vertical depth:
 Bottom Hole Location:

DNR Permit #:
 Will Cores Be Taken?: no
 If yes, proposed zone:

AFFIDAVIT 260' Alt. I Req.

The undersigned hereby affirms that the data...

Pusher Richard Stevenson
 SPUD DATE 7-29-93 INIT. R.C.
 LENGTH SURFACE PLANNED 275
 RESERVE PIT STATUS- REMOVE FLUID LINED
 after salt sect. bbls. when done bbls.
 RATHOLED AHEAD? Y N SIZE HOLE
 SURFACE PIPE 8 3/8 @ 307 CONDUCTOR
 ANHYDRITE T- 284 B- 805 ELEVATION
 TD 4090 FORMATION
 RAN PIPE @ SX DV TOOL SX ALT II DONE Y N
 Arbuckle Plug @ SX Ft. W/ SX
 Hug./Council @ SX Ft. W/ SX
 Anhydrite Base @ 800 Ft. W/ 50 SX
 1/2 Base Anyh. @ SX Ft. W/ SX
 1/2, 1/2 Plug @ SX Ft. W/ SX
 Bottom Surface @ 330 Ft. W/ 50 SX
 40' Plug @ 40 Ft. W/ 10 SX
 RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ SX
 WATER WELL SX (Irr. Well Pond)
 Hauling
 TECHNICIAN R.C. DATE 8-6-93
 TYPE OF CEMENT 20/40 lb 90 gel
 STARTING TIME 8:00 (AM) PM DATE 8-7-93
 COMPLETION TIME 8:00 (AM) PM DATE 8-7-93
 CEMENT COMPANY Allen Drilling Co.