

1 051698

7-29

API NUMBER 15- 185-22,921-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION App.
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SE NE SW, SEC. 9, T 24 S, R 13 WXX

1630 feet from S section line

2315 feet from W section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5097

Lease Name Holmes Well # 1 A

Operator: Martin Oil Producers, Inc.

County Stafford 45.50

Name & Address 150 N. Main, Ste. 1010

Well Total Depth 1400 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 287

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Allen Drilling Company License Number 5418

Address P.O. Box 1389, Great Bend, KS 67530-1389

Company to plug at: Hour: 11:30 a.m. Day: 29 Month: 7 Year: 19 93

Plugging proposal received from Richard

(company name) Allen Drilling Company (phone) 316-793-5681

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 790'

1st plug at 614' with 50 sx cement,

2nd plug at 270' with 50 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None x

Operations Completed: Hour: 12:30 p.m. Day: 29 Month: 7 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug at 614' with 50 sx cement,

2nd plug at 270' with 65 sx cement, cement circulated,

3rd plug to circulate rathole with 15 sx cement.

BOTTOM JOINT OF SURFACE PIPE PARTED.

Remarks: Used 60/40 Pozmix 6% gel by HOWCO.

(If additional description is necessary, use BACK of this form.)

INVOICED

(XXXX / did not) observe this plugging.

DATE 8-9-93

Signed Richard Lacey (TECHNICIAN)

38288 7-29 OCT 06 1993

REC'D 8-2-93 RECEIVED STATE CORPORATION COMMISSION AUG 2 1993

FROM

EFFECTIVE DATE: 7-24-93

X HAD 182:14:28 07/27/93 10-16 LAST SURFACE TOE

FORM MUST BE SIGNED ALL BLANKS MUST BE FILLED

DISTRICT # 1

Well # 1

NOTICE OF INTENTION TO DRILL 185-22,921

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date July 21 1993

Sec 9 Twp 24 S. Rg 13 East NE SW

OPERATOR: License # 5097 Name: Martin Oil Producers, Inc. Address: 150 N. Main #1010 Wichita, KS 67202 Contact Person: Joe Moreland Phone: 316-264-0352

1630 feet from South line of Section 2315 feet from West line of Section IS SECTION REGULAR IRREGULAR

(NOTE: Locate well on the Section Plat on Reverse Side) County: Stafford Lease Name: Holmes Well #: I Field Name: WC

CONTRACTOR: License # 5418 Name: Allen Drilling Co.

Is this a Prepacked/Spaced Field? yes X no

Target Formation(s): Lsg. Arb Nearest lease or unit boundary: 350

Ground Surface Elevation: 1915 feet

Water well within one-quarter mile: yes X no Public water supply well within one mile: yes X no

Depth to bottom of fresh water: 100 Depth to bottom of usable water: 240

Surface Pipe by Alternate: X 1 2 Length of Surface Pipe Planned to be set: (275) 260'

Length of Conductor pipe required: none

Projected Total Depth: 4150

Formation at Total Depth: Arbuckle

Water Source for Drilling Operations: X well farm pond other

DNR Permit #: Will Cores Be Taken? yes X no

If yes, proposed zone: 260' Alt. I Req.

Well Drilled For: Well class: Type Equipment: Oil Enh xec Infield Mud Rotary Gas Storage Peel Ext. Air Rotary CWDG Disposal K. Wildcat Cable Seismic: # of Holes Other

Directional, Deviated or Horizontal wellbore? yes X no If yes, true vertical depth: Section Hole Location:

AFFIDAVIT

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with the 101, et. seq.

Pusher SPUD DATE INIT. LENGTH SURFACE PLANNED RESERVE PIT STATUS- REMOVE FLUID LINED after salt sect. bbls. when done bbls. RATHOLED AHEAD? Y N SIZE HOLE SURFACE PIPE 287 @ 287 CONDUCTOR ANHYDRITE T- 780 B- ELEVATION TD 1400 FORMATION RAN PIPE @ DV TOOL ALT II DONE SX Y N Arbuckle Plug @ Ft. W/ SX Hug./Council @ Ft. W/ SX Anhydrite Base @ 614 Ft. W/ 50 SX 1/2 Base Anhy. @ Ft. W/ SX 1/2, 1/2 Plug @ Ft. W/ SX Bottom Surface @ 220 Ft. W/ 65 SX 40' Plug @ Ft. W/ SX RAT HOLE CIRC/W 5 SX MOUSE HOLE W/ SX WATER WELL SX (Irr. Well Pond Hauling) TECHNICIAN DATE TYPE OF CEMENT STARTING TIME 3:21 AM/PM DATE 29 COMPLETION TIME 3:36 AM/PM DATE 29 CEMENT COMPANY HALLCO 68-90 670 RECEIVED STATE CORPORATION COMMISSION