

1 030507

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 185-22,271-0000

SE NE SE, SEC. 6, T 24 S, R 13 W/X

1650 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5205

Lease Name Fisher Well # 1

Operator: Mid-Continent Energy Corp.

County Stafford 134.23

Name & Address 120 S. Market, Suite 310

Well Total Depth 4130 Arbuckle feet

Wichita, KS 67202

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 259

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A x

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Allen Drilling Co. License Number 5418

Address P. O. Box 1389, Great Bend, KS 67530

Company to plug at: Hour: 6:00 am Day: 5 Month: September Year: 19 85

Plugging proposal received from Gary Christopher

(company name) Allen Drilling (phone) 316-793-5681

Elevation 1914'

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 805'

1st plug into the Arbuckle with 40 sx cement

2nd plug at the base of the Anhydrite with 50 sx cement

3rd plug 30' below the base of the surface pipe

solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 10 sx cement, fill water well with 5 sx cement

Plugging Proposal Received by Steve Durrant

(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 8:00 am Day: 5 Month: September Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 4105' with 40 sx cement, 2nd plug at 815' with 50 sx

cement, 3rd plug at 290' with 40 sx cement, 4th & 5th plugs - solid bridge- hulls - plug

at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with 10

sx cement, and filled water well with 5 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION  
9-6-85  
SEP 6 1985

Remarks: Used 60/40 Pozmix 6% gel by BJ-Titan

(If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION  
Wichita, Kansas

INVOICED

SEP 10 1985

Signed Steve Durrant  
(TECHNICIAN)

DATE

INV. NO.

10012

SEP 09 1985