

6-8-87

To: 1 050908  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 185-22,442-0000  
NE NE SE, SEC. 6, T 24 S, R 13 W/R

TECHNICIAN'S PLUGGING REPORT

Operator License # 5418  
Operator: Allen Drilling Company  
Name &  
Address P.O. Box 1389  
Great Bend, KS 67530

2310 feet from S section line  
330 feet from E section line  
Lease Name Don Fisher Well # 1-6  
County Stafford 134.55  
Well Total Depth 4140 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 796

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Allen Drilling Company License Number 5418

Address P.O. Box 1389, Great Bend, KS 67530

Company to plug at: Hour: 7:30 p.m. Day: 7 Month: 6 Year: 19 87

Plugging proposal received from Allen Cara

(company name) Allen Drilling Company (phone) 316-793-5877

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 1915'  
Anhydrite 786'

1st plug at top of Arbuckle with 50 sx cement, 2nd plug at base Anhydrite with 50 sx cement, 3rd plug at 400' with 40 sx cement, 4th plug at 40' with 10 sx cement, 5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Dick Kapp  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 12:45 a.m. Day: 8 Month: 6 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug at 4090' with 50 sx cement,  
2nd plug at 800' with 50 sx cement,  
3rd plug at 400' with 40 sx cement,  
4th plug at 40' with 10 sx cement,  
5th plug to circulate rathole with 15 sx cement.

Rec'd  
6-11-87

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.

RECEIVED  
STATE CORPORATION COMMISSION

(If additional description is necessary, use BACK of this form.) JUN 11 1987

INVOICED

DATE 6-12-87  
ST. NO. 17222

Signed Richard W. Lacey  
(TECHNICIAN) CONSERVATION DIVISION  
Wichita, Kansas

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date June 1, 1987

API Number 15-185-22-442

OPERATOR: License # 5418
Name ALLEN DRILLING COMPANY
Address P.O. Box 1389
City/State/Zip Great Bend, KS 67530

NE NE SE Sec. 6 Twp. 24 S. Rg. 13 West
2310 Ft. from South Line of Section
330 Ft. from East Line of Section
(Note: Locate well on Section Plat on reverse side)

Contact Person Doug Haisington
Phone 316/793-5877

Nearest lease or unit boundary line 330 feet
County Stafford

CONTRACTOR: License # 5418
Name ALLEN DRILLING COMPANY
City/State Great Bend, KS 67530

Lease Name DON FISHER Well # 1-6
Ground surface elevation 1915 (est.) feet MSL

Well Drilled For: Oil, Gas, OWWO
Well Class: SWD, Inj, Expl
Type Equipment: Mud Rotary, Air Rotary, Cable

Municipal well within 950 feet: yes X no
Municipal well within one mile: yes X no
Depth to bottom of fresh water 180'
Depth to bottom of usable water 250'

If OWWO: old well info as follows:
Operator
Well Name
Comp Date Old Total Depth

Surface pipe by Alternate 1 X 2
Surface pipe planned to be set 800'
Conductor pipe required none
Projected Total Depth 4125 feet
Formation Arbuckle

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.
Date 5/11/87 Signature of Operator or Agent Randall M. Wade Title Exploration Manager

For KCC Use:
Conductor Pipe Required feet; Minimum Surface Pipe Required 250 feet per Alt.
This Authorization Expires 11-12-87 Approved By 5-12-87

Handwritten note: Move in 5-30-87 alt 800 of 800

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays)

Table with 4 columns: Plug #, Depth, Feet depth with, and Size of pipe/gel. Includes entries for 1st through 5th plugs and a rat hole.

Vertical list of well parameters: PUSHER Allen Cara, TD 4140, SURFACE PIPE 8 5/8 @ 796, ANHYDRITE 786, STARTING TIME & DATE 2:30, COMPLETION TIME & DATE 12:45pm 6-8-87, 1st PLUG @ 4090 FT. W/ 50 SX, 2nd PLUG @ 800 FT. W/ 50 SX, 3rd PLUG @ 400 FT. W/ 40 SX, 4th PLUG @ 40 FT. W/ 10 SX, RAT HOLE CIRCULATED W/ 15 SX, MOUSE HOLE CIRCULATED W/ SX, WATER WELL PLUGGED W/ SX, CEMENT COMPANY Halliburton, TECHNICIAN

RECEIVED STATE CONSERVATION COMMISSION JUN 11 1987 CONSERVATION DIVISION Wichita, Kansas