

15-185-22356-0000

11-1

To: 1 061157  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- Drill Completion Date 3/4/86

N/2 SW SW, SEC. 6, T 24 S, R 13 W/EX

990 feet from S section line

4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9281

Lease Name Turner Well # 1-6

Operator: Yager Company

County Stafford 132.76

Name & Address 504 Adair Circle

Well Total Depth 4085 feet

Hutchinson, KS 67502

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 432

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 11 a.m. Day: 1 Month: 11 Year: 19 88

Plugging proposal received from Mark McCabe

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2457

were: 5 1/2" at 4084'

1st plug sand back to 3540' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 50 sx cement at 760',

3rd plug at 460' with 50 sx cement,

4th plug at 40-0' with 10 sx cement.

Plugging Proposal Received by Paul Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 3 p.m. Day: 1 Month: 11 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 3540' and dumped 5 sx cement on top of sand through bailer, loaded hole with mud,

2nd plug pumped 4 sx hulls and 50 sx cement at 760',

3rd plug at 460' with 50 sx cement,

4th plug at 40-0' with 10 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION  
11-3-88  
NOV 5 1988  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used Class A cement with 2% cc. Recovered 2700' of 5 1/2" casing.  
(if additional description is necessary, use BACK of this form.)

INVOICED (check if not) observe this plugging.

Signed Paul A. Luthi (TECHNICIAN)

DATE 11-4-88

INV. NO. 22901