

To: 1 031479  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15- 185-21,358-0000

NW NE SE, SEC. 2, T 24 S, R 14 W/X  
2310 feet from S section line  
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License / 31485  
Operator: Jim Astle  
Name:  
Address: RR 1, Box 22  
St. John, KS 67576

Lease Name Bookstore Well # 1  
County Stafford 137.31  
Well Total Depth 4225 feet  
Conductor Pipe: Size feet  
Surface Casing: Size 8 5/8 feet 350

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Quality Well Service License Number 31925  
Address 249 E. Beth Dr., Sterling, KS 67579

Company to plug at: Hour: 12:20 p.m. Day: 14 Month: 11 Year: 1997

Plugging proposal received from Richard McIntyre

(company name) Quality Well Service (phone) 316-278-2476

were: 5 1/2" at 4155', Perfs at 3741-3850'

1st plug sand back to 3690' and dump 5 sx cement on top of sand through bailer, Recd

2nd plug at 850' with 50 sx cement, 11-18-97

3rd plug at 430' with 50 sx cement,

4th plug at 40' with 10 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 1:45 p.m. Day: 14 Month: 11 Year: 1997

ACTUAL PLUGGING REPORT 1st plug sanded back to 3816' and dumped 5 sx cement on top of sand through bailer,

2nd plug at 850' with 5 sx gel, 1 sx hulls, and 50 sx cement,

3rd plug at 430' with 2 sx gel, 1 sx hulls and 50 sx cement,

4th plug at 40-0' with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 2117' of 5 1/2" casing.  
If additional description is necessary, use BACK of this form.)

I (did ~~not~~) observe this plugging.

DATE 11-21-97

INV. NO. 49556

Signed Steve Durrant (TECHNICIAN)