

6 061493  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

5-17-88 434  
API NUMBER 15- 009-23,514 0000  
NW , SEC. 35 , T 16S, R 15 (W)  
4290 feet from S section line  
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 4656  
Operator: Davis Petroleum Corp  
Name & Address: Box 183 B  
Great Bend, Ks. 67530

Lease Name Hester Well # 1  
County Barton 116.35  
Well Total Depth 3580 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 394

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling Inc. License Number 6050  
Address Box 347 Chase, Ks. 67524

Company to plug at: Hour: 8:00AM Day: 17 Month: May Year: 19 88

Plugging proposal received from Mike Kelso

(company name) Kelso Casing Pulling Inc. (phone) 316-938-2457

were: Order 125 sks Poz 10% Gel 2% Econolite 5 sks Hulls

Plugging Proposal Received by Gilbert G. Scheck  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 10:15AM Day: 17 Month: May Year: 19 88

ACTUAL PLUGGING REPORT 8 5/8" set at 394' w/190 sks. 5 1/2" set at 3579' w/150

sk. Top perf at 3287'. Plugged bottom w/sand and 5 sks cement to 3275'. Shot pipe two  
times and recovered 2300'. Pumped in 8 5/8" 25 sks cement followed w/5 sks Hulls in 100 sks  
cement w/400 Psi.

RECEIVED  
Remarks: By Allied. STATE CORPORATION COMMISSION  
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 6-21-88

INV. NO. 20903

June 6 1988  
06-06-88 Signed Gilbert G. Scheck  
CONSERVATION DIVISION (TECHNICIAN)  
Wichita, Kansas Gilbert Scheck