

1 040152

8-15-88

-00-01

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 151-20,967-A
NE NE SE, SEC. 20, T 29 S, R 14 W/E

TECHNICIAN'S PLUGGING REPORT

2310 feet from S section line
330 feet from E section line

Operator License # 5050

Lease Name Eubank OWWO Well # 1-20

Operator: Hummon Corporation

County Pratt 154.70

Name & Address 400 One Main Place

Well Total Depth 4760 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 10 3/4 feet 331

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635

Address Box 768, Great Bend, KS 67530

Company to plug at: Hour: 9:45 a.m. Day: 15 Month: 8 Year: 19 88

Plugging proposal received from Gary Burke

(company name) Great Bend Casing Pullers (phone) 316-793-9711

were: 4 1/2" at 4736' PBD 4698' Perfs at 4401-03' Elevation 2005' KB

1st plug sand back to 4350' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls and 160 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
AUG 23 1988

Plugging Proposal Received by Paul A. Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:30 a.m. Day: 15 Month: 8 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 4350' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped down 10 3/4" with 300 lbs hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, and 160 sx cement.

Maximum pressure 500 psi and shut in 300 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2844' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
(old) observe this plugging.

DATE 8-24-88

Signed Stephen J. Pfeifer (TECHNICIAN)

INV. NO. 21895