

1 040194

11-26

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-151-21.910-00-00  
SE SW NW, SEC. 15, T 29 S, R 14 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 9408

Operator: Trans Pacific Oil Corporation  
Name & Address 410 One Main Place  
Wichita, KS 67202

2970 feet from S section line  
4290 feet from E section line

Lease Name Chinn Well # 1

County Pratt 152.75

Well Total Depth 4700 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 337

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ O&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Trans Pac Drilling, Inc. License Number 5841

Address 410 One Main Place, Wichita, KS 67202

Company to plug at: Hour: 3:30 p.m. Day: 26 Month: 11 Year: 19 88

Plugging proposal received from Gary Pugh

(company name) Trans Pac Drilling, Inc. (phone) 316-262-3596

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 843-65'

1st plug at 865' with 50 sx cement, 2nd plug at 360' with 40 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Stephen J. Pfeifer  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None

Operations Completed Hour: 5 p.m. Day: 26 Month: 11 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug at 865' with 50 sx cement,

2nd plug at 360' with 40 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(if additional description is necessary, use BACK of this form.)

Observe this plugging.

INVOICED  
DATE DEC 1 1988

Signed Stephen J. Pfeifer  
(TECHNICIAN)

INV. NO. 23219 11-26