

2 030090

To:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 155-20, 975-0000

TECHNICIAN'S PLUGGING REPORT

Operator License # 5142Operator: Sterling Drly. Co.Name & Address Box 129Sterling, Ks. 67579

_____ feet from N/S section line

_____ feet from W/E section line

Lease Name Chisholm Well # 1-10County RenoWell Total Depth 3645 118.47 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8" feet 265'/250 sxAbandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050Address Box 176, Chase, Ks. 67524Company to plug at: Hour: 12:00 N Day: 25 Month: 4 Year: 1984Plugging proposal received from Neil Peddicord(company name) Kelso Csg. Pulling (phone) 316-938-2457were: Sand hole to 3440' dump 5 ex cent. shoot + pull 5 1/2" csg.Pump. cent. down 8 5/8" sur. csg. to plug top of well.(5 1/2" csg. 3640' cent with 175 ex cent., Perfs. 3510' to 3514' - 3496' to 3502'Plugging Proposal Received by Don Thompson
(TECHNICIAN)Plugging Operations attended by Agent?: All X Part _____ None _____Operations Completed: Hour: 12:30 P.M. Day: 25 Month: 12 Year: 1984ACTUAL PLUGGING REPORT Allied Cementing #28564, pumped 40 ex cent down5 1/2" csg. to plug bottom, pumped plug to 3156' at 1650# press.shot and pulled 2765' 5 1/2" csg. Allied Cementing Cementing #28564pumped 2 ex bulls, 6 ex gel, 100 ex 60/40 permix 3% cc down8 5/8" sur. csg. Pump Press. 300# S.I.P. 200#

Remarks: _____

(If additional reservation is necessary, use BACK of this form.)

STATE CORPORATION COMMISSION

If (and only if) observe this plugging.

MAY 02 1984

Signed

Don Thompson
(TECHNICIAN)DATE 5-2-84INV. NO. 13454-25-84CONSERVATION DIVISION
Wichita, KansasFORM CP-2/3
Rev. 01-84

INVOICED