

2 030089

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-155-20, 955-0000

NW NW SW, SEC. 11, T 22 S, R. 10 W/E

_____ feet from N/S section line

_____ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5142

Lease Name Wilson-Schub Well # 1-10

Operator: Sterling Drilg. Co.

County Renov

Name & Address Box 129, 6th + Cleveland

Well Total Depth 3635 118.14 feet

Sterling, Kev. 67579

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 7/8" feet 265' 250' cement

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 176, Chase, Kev. 67524

Company to plug at: Hour: 12:00 N Day: 25 Month: 4 Year: 1984

Plugging proposal received from Neil Peddicard

(company name) Kelso Csg. Pulling (phone) 316-938-2457

were: Sand hole to 3125', dump 5 ex cement, shoot + pull csg., pump cement down 8 7/8" sur. csg. to plug top.

(5 1/2" csg. 3632' cement with 175 ex cement, P.B.T.D. 3250', Perf. 3176' to 3178', 3181' to 3183')

Plugging Proposal Received by Don Thompson
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:00 PM Day: 25 Month: 4 Year: 1984

ACTUAL PLUGGING REPORT Sanded hole to 3117' dumped 5 ex cement (brailer)

shot + pulled 2407' of 5 1/2" csg., Allied Cementing # 32569

pumped 6 ex gel, 2 ex hulls, 100 ex cement down 8 7/8" sur.

csg. Pump Press 500# S.I.P. 200#

RECEIVED
STATE CORPORATION COMMISSION

MAY 02 1984
5-2-84

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Permit 60/40 / 3% cc

(If additional description is necessary, use BACK of this form)

INVOICED

(did / did not) observe this plugging.

DATE 5-2-84

Signed Don Thompson
(TECHNICIAN)

INV. NO. 1346

WL TS

4-25-84