

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

2-070807

API Number: 15-155-20311 - 0000

C NE NW SECTION 12 TWP 22 RANGE 10W

OPERATOR LICENSE #5184 4620 FEET FROM S SECTION LINE
OPERATOR SHIELDS OIL PRODUCERS, INC. 3300 FEET FROM E SECTION LINE
NAME & ADDRESS SHIELDS BLDG
RUSSELL, KS 67665

LEASE NAME BROWN B #1
COUNTY RENO
WELL TOTAL DEPTH 3200' 104.00
PIPE 5 1/2" @ 3192'
SURFACE CASING 8 5/8" @ 212'

ABANDONED OIL WELL GAS WELL INPUT WELL _____ SWD _____ D&A _____

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: QUALITY WELL SERVICE

ADDRESS: STERLING, KS 67579 LICENSE: 31925

COMPANY TO PLUG AT: HOUR: 12:00 DAY: 12 MONTH: 11 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM: JOE MASE

COMPANY NAME: QUALITY WELL SERVICE PHONE: (316) 727-3410

WERE: SAND TO 3140' AND 5 SACKS
35 SACKS @ 1350'
35 SACKS @ 850'
260' TO 0

RECEIVED
KANSAS CORPORATION COMMISSION
NOV 18 1998

PLUGGING PROPOSAL RECEIVED BY: JACK LUTHI


PLUGGING OPERATIONS ATTENDED BY AGENT? ALL PART _____

COMPLETED: HOUR: 7:00 DAY: 12 MONTH: 11 YEAR: 1998

ACTUAL PLUGGING REPORT: COULD NOT GET 5 1/2" CASING LOOSE. SHOT IT SEVERAL TIMES. FINALLY GOT LOOSE AT 1350'. PUMPED 35 SACKS THERE. PULLED TO 850' BUT WE WERE FLOWING ALL THE TIME. SENT FOR 5 SACKS OF GEL AND 200 # OF HULLS. PUMPED 35 SACKS OF CEMENT, 5 SACKS OF GEL AND 200# OF HULLS. THIS SHUT THE FLOW OFF. PULLED TO 260'. CIRCULATED CEMENT TO SURFACE

REMARKS: ALLIED #2596, 60/40 POZ, 4% GEL.

I DID OBSERVE THIS PLUGGING


JACK LUTHI

FORM CP-2/3
REV. 3/90

11-23-98

60369