

4- 070994 6-9

15-051-19503-00-26

D-08,781

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15- -

SE NE SE /4 SEC. 08, 15 S, 18 W
1650 feet from S section line
330 feet from E section line

Operator license# 9346

Lease Ruder D well # SWD

Operator: Diehl Oil

County Ellis

Address: P.O. Box 234
Hays, Kansas 67601
Glenn Diehl

Well total depth 3827 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 146 feet

Aband. oil well ____, Gas well ____, Input well ____, SWD X, D & A __

Plugging contractor: B.J. Services & Express Well Serv. License#

Address: Hays, Kansas and Victoria, Kansas

Company to plug at: Hour: A.M. Day: 9 Month: June Year: 92

Plugging proposal received from: Glen Diehl

Company: Diehl Oil Company

Phone: 913-625-6711

Were: 8 5/8" 146' S.P. cwc. w/146 sx. 5 1/2" casing set @ 3645' w/125
sx.cement. D.V. @ 1160' cwc. w/400 sx.cement. Proposal from Don Butcher.
Run packer test 5 1/2" casing to 960'. Pressured casing to 350 P.S.I.
Shut in @ 100 P.S.I. Fluid @ 700'. Order 200 sx. Class A Common and 400
sx. 65/35 pozmix - 8% gel. w/3 sx. hulls. Run tubing to fish at 1130'.
Spot and displace cement. Load both 5 1/2" casing and 5 1/2" x 8 5/8"
annulus with cement. Shut in under pressure.

Plugging Proposal Received by: Marion Schmidt and Don Butcher

Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 1:00 P.M., Day: 9, Month: June, Year: 92

Actual plugging report: Diehl ordered 200 sx. Class A Common and 400 sx.
65/35 pozmix - 8% gel. and hulls. Spotted and displaced cement through
tubing. 1) 2 3/8" tubing @ 1130'. Spotted 200 sx. Class A Common.
2) 2 3/8" tubing @ 1130' followed with 350 sx. pozmix - 500 P.S.I.
pressure. 3) Laid tubing down - stuck and lost 16 joints tubing.
4) Squeezed 5 1/2" casing w/50 sx. cement. Max. pressure 100 P.S.I.
50 S.I.P. 5) Cement in 5 1/2" x 8 5/8" annulus visible at surface.
Total of 600 sx. cement and 4 sx. hulls mixed in.

Remarks: Cemented by B.J. Services.

Condition of casing(in hole): GOOD BAD X Any plug: YES X NO

Bottom plug(in place): YES X, CALC, NO Dakota plug: YES X NO

Plugged through TUBING X, CASING. Elevation:

I did [x] / did not [] observe the plugging.

DATE 6-26-92

INV. NO. 35573

Form CP-2/3

RECEIVED
STATE CORPORATION COMMISSION
6-16-92
JUN 16 1992
CONSERVATION DIVISION
Wichita, Kansas