

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-175-20387-00-00
Spot: NWSW Sec/Twnshp/Rge: 21-34S-32W
1940 feet from S Section Line, 4488 feet from E Section Line
Lease Name: COOPER TWIN Well #: 1
County: SEWARD Total Vertical Depth: 6214 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S MARKET
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5340		WITH 2 SX CMT
PROD	4.5	6214	1760	WITH 250 SX CMT
SURF	8.625	1448		WITH 150 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 01/05/2016 9:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: SET CIBP @ 5850' WITH 2 SX CMT ON TOP. PRESSURE TEST CASING TO 300 PSIG. IF CASING PRESSURE TESTS OUT, FREE POINT & SHOOT CASING FREE. PULL CASING TO 1510' & PUMP 20 SX GEL & 50 SX CMT. PULL CASING TO 530' & SPOT 40 SX CMT. PULL CASING TO 40' & PUMP 20 SX CMT. IF CASING DOESN'T TEST OUT USE TBG.

Plugging Proposal Received By: SCOTT ALBERG Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/05/2016 12:00 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

SET CIBP @ 5340' WITH 2 SX CMT ON TOP. (AS DEEP AS THEY COULD GET). CUT CASING AT 1760' & PULL OUT OF HOLE. RUN TBG IN HOLE TO 1488'. 1ST PLUG AT 1488' WITH 18 SX GEL & 50 SX CMT. 2ND PLUG AT 527' WITH 40 SX CMT. 3RD PLUG AT 62' WITH 35 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5882	5888		

KCC WICHITA
JAN 13 2016
RECEIVED

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY. CONTROL NO. 20160020-001

Plugged through: TBG

District: 01

RECEIVED
JAN 08 2016
KCC DODGE CITY

Signed Kenny Sullivan
SA (TECHNICIAN)