

1052370

15-185-10977-00-00

TO: STATE CORPORATION COMMISSION

API NUMBER 15-185-22,726  
SW SW SE SEC. 8, T 24 S, R 12 W

CONSERVATION DIVISION - PLUGGING SECTION 330 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 2310 FEET FROM EAST SECTION LINE  
~~3630~~

WICHITA, KANSAS 67202

LEASE NAME O'CONNOR WELL # 1

TECHNICIAN'S PLUGGING REPORT 2/9

COUNTY STAFFORD \$125.91

OPERATOR LICENSE # 3911

WELL TOTAL DEPTH 3874 FEET

OPERATOR: RAMA OPERATING CO., INC. PRODUCTION CSG: SIZE 5 1/2" @ 3870' WITH 125 SX

NAME AND PO BOX 159 SURFACE CASING: SIZE 8 5/8" @ 205' WITH 200 SX

ADDRESS STAFFORD, KS 67578

ABANDONED OIL WELL X GAS WELL \_\_\_\_\_ INPUT WELL \_\_\_\_\_ INJ WELL \_\_\_\_\_ D/A \_\_\_\_\_

OTHER WELL AS HEREINAFTER INDICATED \_\_\_\_\_

PLUGGING CONTRACTOR MIKE'S TESTING & SALVAGE, INC LICENSE NUMBER 31529

ADDRESS PO BOX 467, CHASE, KS 67524-0209

COMPANY TO PLUG AT: HOUR: 2:30 PM DAY: 09 MONTH: 02 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM MONTE ANDREWS

(COMPANY NAME) MIKE'S TESTING & SALVAGE (PHONE) 316-938-2945

WERE: OPEN HOLE 3870-74.

1ST PLUG SANDED TO 3800' AND 5 SX CEMENT WITH BAILER. SPOTTED PLUGS THROUGH CASING.

2ND PLUG AT 710' WITH 10 SX GEL & 50 SX CEMENT. 3RD PLUG AT 230' WITH 40 SX CEMENT.

4TH PLUG AT 40' WITH 10 SX CEMENT.

\_\_\_\_\_ PLUGGING PROPOSAL RECEIVED BY RICHARD LACEY

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART \_\_\_\_\_ NONE \_\_\_\_\_

OPERATIONS COMPLETED: HOUR: 3:35 PM DAY: 09 MONTH: 02 YEAR: 2000

ACTUAL PLUGGING REPORT \_\_\_\_\_

1ST PLUG SANDED TO 3800' AND 5 SX CEMENT WITH BAILER. SPOTTED PLUGS THROUGH CASING.

2ND PLUG AT 710' WITH 10 SX GEL & 50 SX CEMENT. 3RD PLUG AT 230' WITH 40 SX CEMENT.

4TH PLUG AT 40' WITH 10 SX CEMENT.

RECEIVED  
STATE CORPORATION COMMISSION

2-15-00  
FEB 15 2000

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 1900' OF 5 1/2" CASING  
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM)  
Conservation Division  
Wichita, Kansas

I (DID) OBSERVE THIS PLUGGING

**INVOICED**

SIGNED Richard W. Lacey  
(TECHNICIAN)

DATE 2/15/00

FORM CP-2/3

INV. NO. 061254