

To: 1 052207  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

12-15

API NUMBER 15- Drilled 2/1/62  
N/2 SE SW, SEC. 8, T 24 S, R 12  
990 feet from S section line  
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License / 3911  
Operator: RAMA Operating Inc.  
Name & Address: P.O. Box 159  
Stafford, KS 67578

Lease Name Jordan Well # 2  
County Stafford 125.42  
Well Total Depth 3859 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 236

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Mike's Testing & Salvage, Inc. License Number 31529  
Address P.O. Box 467, Chase, KS 67524

Company to plug at: Hour: 2 p.m. Day: 15 Month: 12 Year: 19 97

Plugging proposal received from Manny Boatwright

(company name) Mike's Testing & Salvage, Inc. (phone) 316-938-2943

logs: 5 1/2" at 3856' w/75 sx cement, Perfs from 3635-3769' (7 sets)

1st plug sand back 50' above perfs and dump 5 sx cement on top of sand through bailer,

2nd plug at 700' with 50 sx cement,

3rd plug at 270' with 50 sx cement,

4th plug at 40' with 10 sx cement.

Rec'd  
12-18-97

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 3:30 p.m. Day: 15 Month: 12 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug sanded back to 3580' and dumped 5 sx cement on top of sand through bailer,

Pumped plugs through casing:

2nd plug at 720' with 50 sx cement,

3rd plug at 270' with 50 sx cement,

4th plug at 40' with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2000' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED

I (did not) observe this plugging.  
DATE JAN 08 1998

INV. NO. 49838

Signed Richard W. Lucy (TECHNICIAN)