

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-22726-00-00
Spot: SWSESW Sec/Twnshp/Rge: 8-24S-12W
330 feet from S Section Line, 3630 feet from E Section Line
Lease/Unit Name: V BARTLETT Well Number: 1
County: STAFFORD Total Vertical Depth: 4100 feet

Operator License No.: 3911
Op Name: RAMA OPERATING CO., INC.
Address: 101 S. MAIN
STAFFORD, KS 67578

Conductor Pipe: Size _____ feet:
Surface Casing: Size 8.625 feet: 277 WITH 225 SX CMT \$ 133.25
Production: Size 5.5 feet: 4095 WITH 150 SX CMT
Liner: Size _____ feet:

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/05/2001 9:30 AM

Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC. Phone: (316) 938-2537

Proposed Plugging Method: SAND TO 3620' & 5 SX CMT. 1ST PLUG AT 720' WITH 50 SX CMT & 10 SX GEL. 2ND PLUG AT 300' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: RICHARD LACEY
Date/Time Plugging Completed: 02/05/2001 12:05 PM

Witness Type: Plugging Operations 100% Witnessed (Complete)
KCC Agent: RICHARD LACEY

Actual Plugging Report:

PBTD 3775'. PERFS AT 3670-73 & 3706-12'. ANHYDRITE @ 710'. SAND TO 3610' AND DUMP 5 SX CMT ON SAND WITH DUMP BAILER. PUMP PLUGS THROUGH CASING WHILE PULLING. 1ST PLUG AT 742' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 326' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

INVOICED

DATE 03-07-2001

INV. NO. 2001061435

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2427' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

Signed Richard W. Lacey
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
2-14-01
FEB 14 2001

FEB 13 2001

CONSERVATION DIVISION
Wichita, Kansas

Form CP-2/3