

To: 1 120678
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

15-185-21360-0000
API NUMBER 15- Docket #D-20,323

TECHNICIAN'S PLUGGING REPORT
Operator License # 3911
Operator: RAMA Operating Company, Inc.
Name:
Address P.O. Box 159
Stafford, KS 67578

W/2 NE NE SEC. 8, T. 24 S, R 12 W/E
4620 feet from S section line
990 feet from E section line
Lease Name Knoche Well # 2
County Stafford
Well Total Depth 4184 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 251

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well X D&A
Other well as hereinafter indicated _____

Plugging Contractor Pipe Recovery Inc. License Number _____
Address P.O. Box 7, Great Bend, KS 67530

Company to plug at: Hour: 8:30 a.m. Day: 10 Month: 2 Year: 19 92

Plugging proposal received from Rick Davis

(company name) Pipe Recovery, Inc. (phone) 316-793-3922

were: 5 1/2" at 4033', Tubing at 2800'

1st plug sand back to 2750' and dump 4 sx cement on top of sand through bailer,
2nd plug pump in 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx
gel, 100 lbs. hulls, release 8 5/8" wiper plug and pump 125 sx cement.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 10:40 a.m. Day: 10 Month: 2 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 2800' and dumped 5 sx cement
on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement,
10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Pumping pressure 0-700 psi and shut in 100 psi.

RECEIVED
STATE CORPORATION COMMISSION
FEB 13 1992
2-13-92
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1389' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
Observe this plugging.

Signed Susan Rankin
(TECHNICIAN)

DATE 2-21-92
WEL. NO. 34622