

1 120836

9-27

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-185-20,892-0000  
NW NW SW, SEC. 3, T 24 S, R 14 W/4  
2310 feet from S section line  
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5393  
Operator: A.L. Abercrombie, Inc.  
Name:  
Address Rt. 1, Box 56  
Great Bend, KS 67530

Lease Name Jerel Well # 1  
County Stafford  
Well Total Depth 4250 138.12 feet  
Conductor Pipe: Size feet  
Surface Casing: Size 8 5/8 feet 459

Abandoned Oil Well  Gas Well  Input Well  SWD Well  O&A   
Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050  
Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 1 p.m. Day: 27 Month: 9 Year: 19 93

Plugging proposal received from Mike Kelso  
(company name) Kelso Casing Pulling (phone) 316-938-2943

were: 4 1/2" at 4248' w/250 sx cement, PBTD 4194', Perfs at 3798-3804, 3837-40'  
1st plug sand back to 3750' and dump 4 sx cement on top of sand through bailer,  
2nd plug pump in 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel,  
100 lbs. hulls, release 8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None   
Operations Completed: Hour: 2:30 p.m. Day: 27 Month: 9 Year: 1993

ACTUAL PLUGGING REPORT 1st plug sanded 4 1/2" casing back to 3750' and dumped 4 sx cement on  
top of sand through bailer,  
2nd plug pumped into 8 5/8" surface casing with 100 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx  
gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Pumping pressure 0-600 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1900' of 4 1/2" casing.  
Additional description is necessary, use BACK of this form.

DATE (did I observe this plugging.)

Signed Duane Rankin (TECHNICIAN)

INVOICE # 38887

RECEIVED STATE CORPORATION COMMISSION 10-6-93 OCT 06 1993 CONSERVATION DIVISION Wichita, Kansas