

115

4-10

R

To: 1-120402  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 185-22,456-0000  
SW NW SW, SEC. 22, T 24 S, R 12 W/E  
1650 feet from S section line  
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6988

Lease Name Erhart Well # A-1

Operator: Smith Oil Operations

County Stafford 134.26

Name & Address P.O. Box 550

Well Total Depth 4131 feet

Hutchinson, KS 67504-0550

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 221

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 10 a.m. Day: 10 Month: 4 Year: 19 90

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: 5 1/2" at 4124' PBT 3922' Perfs at 3552-3928' (7 sets)

1st plug sand back to 3500' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11:30 a.m. Day: 10 Month: 4 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 3500' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Pumping pressure 0-450 psi and shut in 150 psi.

REC'D 4-18-90

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 2721' of 5 1/2" casing. (If additional description is necessary, use BACK of this form.)

INVOICED

observed this plugging.

DATE 4-25-90

Signed Dianne Roshin (TECHNICIAN)

INV. NO. 27964

RICHARD E. SMITH  
HUTCHINSON, KS 87504-0550

22-24 -12W  
SW NW SW

#1 ERHART "A"

site: 3/4 S & 1-1/2 W OF STAFFORD, KS	city: STAFFORD	API 15-185-22456
contr: DUKE DRILLING COMPANY, INC	field: NORTH STAR	
oper: BOB LEWELLYN		
fr date 08/26/87	spd date 09/01/87	drig comp 09/10/87
		card issued 01/13/88
		last revised 01/13/88


ELV: 1882 KB LOG  
tops.....depth/datum

\*ANH .....689 +1193  
HEEB .....3323 -1441  
DOUG .....3358 -1478  
BR LM .....3480 -1598  
LANS .....3507 -1825  
BKC .....3794 -1912  
VIOLA .....3910 -2028  
SIMP .....4036 -2154  
ARB .....4096 -2214  
RTD .....4126 -2244  
LTD .....4131 -2249  
\*SAMPLE TOP

IP status:  
OIL WELL, LKC 3552-3760 OA, VIOLA 3900-3901  
CSG: 8-5/8" 221 / 140 SX, 5-1/2" 4124 / 175 SX  
NO CORES  
DST (1) 3580-3594 (LKC), / 30-30-120-60, REC 280' W,  
IFP PLUGGING ISIP 1312# FSIP 1221# FFP 162# IHP  
1753# FHP 1722# BHT 112 "

(over)

COPYRIGHT 1987  
INDEPENDENT OIL & GAS SERVICE, INC.  
WICHITA, KANSAS

RICHARD E. SMITH  
HUTCHINSON, KS 87504-0550

22-24 -12W  
SW NW SW

#1 ERHART "A"

DST (2) 3897-3909 (VIOLA), / 30-30-30-30, REC 15' HVY DM ISIP 683# FSIP 683# IFP 30#  
FFP 46# IHP 1982# FHP 1950# BHT 110 "

DST (3) 3903-3915 (VIOLA), / 30-45-120-90, REC 270' W, W / SOME FREE OIL ISIP 714# FSIP  
714# IFP 90# FFP 160# IHP 1924# FHP 1890# BHT 113 "

DST (4) 4100-4106 (ARB), / 30-45-120-90, 1800' SULPHUR WTR, W / SCUM OIL ISIP 1427#  
FSIP 1427# IFP 96# FFP 722# IHP 2021# FHP 1972# BHT 121 "

MICT - CO, PF (LKC) 3552-3554, W / 2 SPF, AC 500 GAL, GSO, PF (LKC) 3647-3650, W / 2 SPF,  
AC 1000 GAL, GSO, PF (LKC) 3688-3692, W / 2 SPF, AC 1000 GAL, GSO, PF (LKC) 3718-3722,  
W / 2 SPF, AC 1000 GAL, GSO, PF (LKC) 3757-3760, W / 2 SPF, AC 1000 GAL, GSO, PF (VIOLA)  
3900-3901, W / 2 SPF, AC 300 GAL, GSO, PF (VIOLA) 3926-3928, W / 2 SPF, AC 250 GAL, NS,  
SET SET PERM BP AT 3922, T&R, POP, OIL WELL (POTENTIAL NOT RPTD), 12/9/87,  
COMMINGLED

RECEIVED  
STAT  
FEB 20 1990  
CONSERVATION DIVISION  
Wichita, Kansas