

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
211 NORTH BROADWAY
WICHITA, KANSAS

WELL PLUGGING APPLICATION FORM
File One Copy

Lease Owner Cities Service Oil Co. Address Box 751, Great Bend, Kansas
(Applicant)

SE NW SW
Lease (Farm Name) Kelly "B" Well No. 1

Well Location 990' S. & 990' E. of W/4 Cor. Sec. 4 Twp. 24 Rge. 12 (E) - (W) West

County Stafford Field Name (if any) -

Total Depth 3941 - PB 3925 Oil Gas X Dry Hole

Was well log filed with application? Yes If not, explain:

Log attached.

Date and hour plugging is desired to begin As soon as possible.

Plugging of the well will be done in accordance with the Rules and Regulations of the State Corporation Commission.

Name of the person on the lease in charge of well for owner

V. M. Conover Address Box 751, Great Bend, Kansas

Plugging Contractor Walker Drilling, Inc.

Plugging Contractor's License No. ----

Address Great Bend, Kansas

Invoice covering assessment for plugging this well should be sent to

Cities Service Oil Company Address Box 751, Great Bend, Kansas

and payment will be guaranteed by applicant.

RECEIVED
CORPORATION COMMISSION

V. M. Conover
Applicant or Acting Agent

Date August 8, 1955.

PLUGGING
FILED SEC 4 T 24 R 12 W
BOOK PAGE 141 LINE 17

Rec'd
8-10-55

CONSERVATION DIVISION
KANSAS



STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
211 NORTH BROADWAY
WICHITA, KANSAS

August 10, 1955

Well No.	
Lease	
Description	1
County	Kelly "B"
File No.	SE NW SW 14-24-12W Stafford 141-19

Citios Service Oil Company
Box 751
Great Bend, Kansas

~~Confidential~~

This letter is your authority to plug the above subject well, in accordance with the Rules and Regulations of the State Corporation Commission. When you are ready to plug this well, please contact our District Plugging Supervisor, Mr.

Warren H. Horner, Box 207, STATE CORPORATION COMMISSION
CONSERVATION DIVISION

BY: S. S. Greider
S. S. Greider
WELL PLUGGING SUPERVISOR

cc:
District Plugging Supervisor

WELL RECORD

Company Cities Service Oil Co. Well No. 1 Farm Kelly "B"
 Location 990' South and 990' East of W/4 Corner Sec. 4 T. 24 R. 12W
 Elevation 1879 (1877 Gr.) County Stafford State Kansas
 Drlg. Comm. March 8, 1952 Contractor H. W. Rine Drilling Co.
 Drlg. Comp. March 19, 1952 Acid. 500 gals. 3-27-52; 1000 gals. 3-29-52
 T. D. 3941' Initial Prod. B. P. Ind. Capacity 6,200 M. C. F. gas (6-9-52)
 P. D. 3925'

CASING RECORD:

8-5/8" @ 313' cen. 250 sz cement
 5-1/2" @ 3941' cen. 150 sz cement

FORMATION RECORD:

clay, sand, shale & shells	0-316
shale & shells	1770
lime & shale	1910
shale & lime	2065
lime	2200
lime & shale	2500
shale & lime	2900
lime	3330
shale & lime	3470
lime	3770
lime & chert	3799
lime	3811
lime & chert	3860
cherty lime	3910
lime & chert	3920
lime	3945

3945 BTD = 3941 SLM

Corr. Brown Limestone	3431'
Corr. Lansing	3456'
Corr. Viola	3793'
Corr. Simpson	3926'
Penetration	15'
Total Depth	3941'

Drilled cement to 3925 S. L. M.

Perf. 48 shots 3820-30.

3-27-52 Az. 500 gals. 3820-30.

2,900 M. C. F. gas through 2" tubing;
S. I. P. 950%.Killed well and set Baker plug at
3815 S. L. M.

Perf. 56 shots 3795-3809.

3-29-52 Az. 1000 gals. 3795-3809.

Drilled bridge plug to 3925.

4-4-52 5,020 M. C. F. gas through
2"; S. I. P. 965%.

5XFO:	500'	0°
	1000'	1°
	1500'	0°
	2000'	1°
	2500'	1°
	3000'	0°
	3500'	1°

RECEIVED

PLUGGING

FILE SEC 4 T24 R 12W

BOOK PAGE 141 LINE 19 DIVISION
1952, Kansas