

To: 1 120612
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 3911
Operator: RAMA Operating Company, Inc.
Name:
Address: P.O. Box 159
Stafford, KS 67578

8-28 15-185-20501-0000 365
API NUMBER 15- NA
SE SE NW, SEC. 4, T 24 S, R 12 W/E
2970 feet from S section line
2970 feet from E section line
Lease Name Metz Well # 1
County Stafford 127.82
Well Total Depth 3933 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 212

Abandoned Oil Well ☒ Gas Well ☒ Input Well ☐ SWD Well ☐ D&A ☐
Other well as hereinafter indicated
Plugging Contractor Kelso Casing Pulling License Number 6050
Address P.O. Box 347, Chase, KS

Company to plug at: Hour: 9 a.m. Day: 28 Month: 8 Year: 19 91

Plugging proposal received from Millard Kelso
(company name) Kelso Casing Pulling (phone) 316-938-2943

were: 4 1/2" at 3925' w/175 sx cement, PBSD 3816', Perfs at 3668-3712'.

1st plug sand 4 1/2" casing back to 3615' and dump 4 sx cement on top of sand through bailer,

2nd plug pump in 8 5/8" surface casing with 400 lbs. hulls, 10 sx gel, 50 sx cement,

10 sx gel, 100 lbs. hulls, release 8 5/8" wiper plug and pump 125 sx cement.

Plugging Proposal Received by Duane Rankin
(TECHNICIAN)

Plugging Operations attended by Agent?: All ☒ Part ☐ None ☐

Operations Completed: Hour: 12 p.m. Day: 28 Month: 8 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug sanded 4 1/2" casing back to 3616' and dumped 4 sx cement
on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 400 lbs. hulls, 10 sx gel, 50 sx cement,

10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Pumping pressure 0-200 psi and shut in 50 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1500' of 4 1/2" casing.

INVOICED
(If additional description is necessary, use BACK of this form.)
observe this plugging.

DATE 9-13-91
INV. NO. 33115

Signed Duane Rankin
(TECHNICIAN)