

1 080402

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 185-22,202-0000

SE SW NE, SEC. 7, T 24 S, R 12 (W) & E

2970 feet from S section line

1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5003

Lease Name Bartlett Well # 1

Operator: McCoy Petroleum Company

County Stafford 134.88

Name & Address 500 Heritage Park Place

Well Total Depth 4150 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 264

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Clarke Corporation License Number 5105

Address P. O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 10:00 am Day: 12 Month: September Year: 19 85

Plugging proposal received from Elmo Morgenstern

(company name) Clarke (phone) 316-886-5665

were: 5 1/2" at 4148' PBTD 4137', Perfs at 3538-3542'

1st plug sand back to 3488' and dump 5 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 10 sx gel, 50 sx cement, 15 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump 125 sx cement.

Plugging Proposal Received by J. A. Mel (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 11:15 am Day: 12 Month: July Year: 19 85

ACTUAL PLUGGING REPORT 1st plug sanded back to 3488' and dumped 5 sx cement on top

of sand through bailer, 2nd plug squeezed well with 3 sx hulls, 10 sx gel, 50 sx cement, 15 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 125 sx cement.

RECEIVED STATE CORPORATION COMMISSION Rec'd 7-22-85

Maximum pressure 600 psi and shut in 400 psi PL

Remarks: Recovered 2009' 5 1/2" casing. Used 60/40 Pozmix 6% gel by BJ-Titan (If additional description is necessary, use BACK of this form.)

INVOICED

DATE 7-24-85

Signed J. A. Mel (TECHNICIAN)

INV. NO. 9096