

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-167-01645-00-02
Spot: SESWNW Sec/Twnshp/Rge: 22-13S-14W
feet from Section Line, feet from Section Line
Lease Name: ANCHUTZ OWWO Well #: 3
County: RUSSELL Total Vertical Depth: 860 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S MARKET
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	639	639	Unknown sx cement
SURF	7	3275		Unknow sx cement

Well Type: EOR UIC Docket No: _____ Date/Time to Plug: 01/16/2014 8:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: KCC Phone: (620) 727-3410

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/200 # hulls.
No 4 1/2" casing found in well.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/17/2014 4:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 713' and pumped 260 sx cement w/100 # hulls. Pulled tubing to 375' and pumped 65 sx cement w/100 # hulls. Cement circulated. POOH. Hooked to casing and shut in.
01/17/2014- Pumped 85 sx cement w/3% cc. Achieved pressure and shut in.
GPS: 38.90836 -098.86966

Perfs:


KCC WICHITA
JAN 13 2016
RECEIVED

Remarks: QUALITY WELL SERVICE TICKET # 6107 ANSCHUTZ FEE FUND PROJECT CONTROL # 20140043001

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

CM

JAN 07 2016

Form CP-2/3