

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-007-20991-00-00  
Spot: NWNWSW Sec/Twnshp/Rge: 12-32S-12W  
2310 feet from S Section Line, 330 feet from W Section Line  
Lease Name: DOHERTY Well #: 4  
County: BARBER Total Vertical Depth: 4285 feet

Operator License No.: 33168  
Op Name: WOOLSEY OPERATING COMPANY, LL  
Address: 125 N MARKET STE 1000  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4180		WITH 2 SX CMT
PROD	5.5	4299	0	WITH 75 SX CMT
SURF	8.625	210		WITH 185 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/06/2016 9:00 AM  
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION  
Proposal Rcvd. from: MARK MORGENSTERN Company: CLARKE CORPORATION Phone: (620) 886-5665

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 01/06/2016 10:00 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

\*\*10/29/04: PUMPED DOWN 5 1/2" X 8 5/8" ANNULUS WITH 150 SX 60/40 POZMIX 6% GEL CMT. RATE 3 BPM @ 350#. SIP 500#.\*\* SET CIBP @ 4180' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. PUMPED THROUGH 2 3/8" TBG WITH 100 SX CMT FILLING 5 1/2" CASING FROM 600' TO SURFACE WITH CMT. PUMPED DOWN 5 1/2" X 8 5/8" ANNULUS WITH 1 SX CMT PRESSURING UP TO 700#. LAID TBG DOWN & TOPPED OFF 5 1/2" CASING WITH 5 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4254	4260		
4238	4244		
4230	4238		

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: TBG

District: 01

Signed Stephen J. Pfeifer  
(TECHNICIAN)  
KCC WICHITA

RECEIVED  
JAN 07 2016  
KCC DODGE CITY

JAN 11 2016  
RECEIVED

Form CP-2/3  
20  
1-15-2016