

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-30833-00-00
Spot: SWSWNW Sec/Twnshp/Rge: 33-18S-11W
2970 feet from S Section Line, 4950 feet from E Section Line
Lease Name: ST PETER Well #: 2-1
County: BARTON Total Vertical Depth: 3424 feet

Operator License No.: 5011
Op Name: VIKING RESOURCES, INC
Address: 400 N WOODLAWN ST, STE 18
WICHITA, KS 67208

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	7	3404		5 SX
SURF	10	640		5 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/16/2015 8:00 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: SHAWN DEVLIN Company: VIKING RESOURCES Phone: (316) 262-2502

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement, 2100 # gel and 600 # hulls.

Plugging Proposal Received By: BRUCE RODIE Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/18/2015 3:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 1350' and 600'. Ran tubing to 3270' and pumped 2100 # gel followed by 75 sx common cement w/3% cc and 300 # hulls. Pulled tubing to 1350' and pumped 130 sx cement w/300 # hulls. Pulled tubing to 600' and pumped 120 sx cement. Pulled tubing. Tied to surface pipe and pumped 50 sx cement and pushed cement up casing. Topped off casing w/40 sx cement and shut down for the day.
12/18/2015-Topped off casing with 20 sx cement.

GPS: 38.44304 -098.55320

Perfs:

Top	Bot	Thru	Comments
3158	3172		
3146	3150		

Remarks: SWIFT SERVICES

Plugged through: CSG

District: 04

Signed

Bruce Rodie
(TECHNICIAN)

CM

DEC 30 2015

Form CP-2/3

no
1-15-2016