

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-195-01369-00-00
Spot: SWNWSE Sec/Twnshp/Rge: 26-12S-22W
1650 feet from S Section Line, 2310 feet from E Section Line
Lease Name: OGALLAH UNIT Well #: 4-7
County: TREGO Total Vertical Depth: 3983 feet

Operator License No.: 6569
Op Name: CARMEN SCHMITT, INC.
Address: PO BOX 47
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3968		150 SX
SURF	8.625	251		175 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/05/2016 1:00 PM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: CURTIS HITSCHMANN Company: CARMEN SCHMITT, INC. Phone: (620) 793-2540

Proposed Plugging Method: Ordered 550 sx 60/40 pozmix 4% gel cement w/600 # hulls.
Perforations: 3969' - 3983'.

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/05/2016 6:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Shot perforations at 2350', 1735', 925' and 245'. Ran tubing to 3938' and pumped 100 sx cement w/200 # hulls. Pulled tubing to 3716' and pumped 100 sx cement w/150 # hulls. Pulled tubing to 2824' and pumped 100 sx cement w/150 # hulls. Pulled tubing to 1727' and pumped 80 sx cement. Good circulation of cement. Pulled tubing and topped off casing w/25 sx cement. Tied on to backside, pumped 40 sx cement and shut in.

GPS: 38.975895 -099.73198

Perfs:

Top	Bot	Thru	Comments
3969	3983		

KCC WICHITA
JAN 13 2016
RECEIVED

Remarks: COPELAND ACID AND CEMENTING TICKET # 43615

Plugged through: TBG

District: 04

Signed


(TECHNICIAN)

CM

JAN 07 2016

Form CP-2/3

no
1-15-2016