

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-007-16643-00-00  
Spot: NWSESW Sec/Twnshp/Rge: 31-33S-12W  
971 feet from S Section Line, 3664 feet from E Section Line  
Lease Name: DONOVAN B Well #: 1  
County: BARBER Total Vertical Depth: 4680 feet

Operator License No.: 3959  
Op Name: SIROKY OIL MANAGEMENT  
Address: PO BOX 464  
PRATT, KS 67124

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4500		WITH 2 SX CMT
PROD	5.5	4677	510	WITH 100 SX CMT
SURF	8.625	295		WITH 250 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/23/2015 2:00 PM  
Plug Co. License No.: 34227 Plug Co. Name: AMERICAN WELL SERVICE LLC  
Proposal Rcvd. from: SPENCER SIROKY Company: AMERICAN WELL SERVICE LLC Phone: (620) 672-5625

Proposed Plugging Method: SET CIBP @ 4500' & 2 SX CMT. PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. PLUG AT 300' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 12/23/2015 4:15 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 4500' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. ATTEMPTED TO LOAD 5 1/2" CASING. WOULD NOT LOAD DUE TO CASING LEAK. TRIED PULLING STRETCH IN 5 1/2" CASING. VERY LITTLE STRETCH. SHOT CASING AT 650'. PIPE STILL HUNG UP. SHOT UP AT 510' & CAME LOOSE. LAID DOWN 5 1/2" CASING. RAN TBG IN TO PLUG THROUGH. 1ST PLUG AT 515' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 320' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4587	4604		

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA HIGH FL & SI 10 YRS\*\* USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: TBG

District: 01

Signed

*Stephen J. Pfeifer*  
TECHNICIAN  
KCC WICHITA

RECEIVED  
JAN 07 2016  
KCC DODGE CITY

JAN 11 2016  
RECEIVED

Form CP-2/3

*20*  
*1-15-2016*