

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-001-31408-00-00
Spot: SWSWSWNW Sec/Twnshp/Rge: 29-23S-20E
2892 feet from S Section Line, 5028 feet from E Section Line
Lease Name: FLEWHARDY Well #: B2
County: ALLEN Total Vertical Depth: 1180 feet

Operator License No.: 6168
Op Name: SCHEUNEMAN, LESTER
Address: 27800 PLEASANT VALLEY RD
WELLSVILLE, KS 66092

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.875	1175		60 SX
SURF	7	21		4 SX

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 11/09/2015 12:00 AM
Plug Co. License No.: 4339 Plug Co. Name: JACKSON, DALE E & SUE ELLEN DBA DALE E. JACKSON PRODUCTI
Proposal Rcvd. from: _____ Company: _____ Phone: _____

Proposed
Plugging
Method:

Plugging Proposal Received By: _____ WitnessType: NONE
Date/Time Plugging Completed: 11/09/2015 8:00 AM KCC Agent: RYAN DULING

Actual Plugging Report:

Perfs:

Ran 1" pipe to 1175'. Pumped 800 gal of water mixed with 50lbs sodium benetite through the 1" pipe. Pumped 9 sacks of cement through the 1" pipe. Pulled 1" pipe up to 550'. Pumped 9 sacks of cement through the 1" pipe at 550'. Pulled 1" pipe up to 250'. Pumped and circulated cement through the 1" pipe from 250' to surface. Pulled the 1" pipe out of the well and topped the well off with cement. A total of 60 sacks of portland cement was reported used to plug this well.

RECEIVED
KCC DIST # 3
JAN 06 2016
CHANUTE, KS

RD

Remarks:

Plugged through: TBG

District: 03

Signed [Signature]
(TECHNICIAN)

KCC WICHITA

JAN 11 2016

RECEIVED

Form CP-2/3

1-15-2016
MO