

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

Stafford County, Sec. 8 Twp. 24S Rge. 12 (W)

Location as "NE/CNW%SW%" or footage from lines A/C SW/4 SE/4 NW/4

Lease Owner Barnett Oil Company

Lease Name Bartlett Well No. 1

Office Address 411 First Nat'l Bank Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed October 10, 19 61

Application for plugging filed October 10, 19 61

Application for plugging approved October 12, 19 61

Plugging commenced October 10, 19 61

Plugging completed October 10, 19 61

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Frank Broadfoot

Producing formation Depth to top Bottom Total Depth of Well 3890 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	194 1/2'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with mud to 195'. Pushed plug to 195' with 1/2 sack of hulls on top. Cemented with 20 sacks of cement through drill pipe. Filled hole with mud to 40'. Pushed plug to 40' and wired with 1/2 sack of hulls on top. Cemented to surface with 15 sacks.

Plugged rat hole with 3 sacks of cement.

Plugging completed at 4:00 P.M., 10/10/61.

RECEIVED  
STATE CORPORATION COMMISSION  
10-20-61  
OCT 20 1961

(Copy of Well Log attached)

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Barnett Drilling, Inc.

Address 409 First National Bank Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
F. H. Rousey

(employee of owner, lessee or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) F. H. Rousey  
411 First Nat'l Bank Bldg., Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 19th day of October, 19 61

My commission expires February 27, 1964.

Mildred J. Willis  
Notary Public.



BARNETT OIL COMPANY  
WELL LOG - BARTLETT NO. 1  
A/C SW/4 SE/4 NW/4 SECTION 8-24S-12W  
STAFFORD COUNTY, KANSAS

---

<u>From</u>	<u>To</u>	<u>Formation</u>
0	30	Clay
30	90	Sand
90	160	Sand and shale
160	195	Shale
195	250	Shale and red bed
250	685	Shale and shells
685	715	Anhydrite
715	905	Shale
905	1455	Shale and shells
1455	2200	Shale and Lime
2200	2315	Shale
2315	2710	Shale and Lime
2710	3500	Lime and shale
3500	3871	Lime
3871	3890	Chert (T.D.) (D. & A.)

Set 8 5/8", 28# casing at 194½'  
with 200 sacks of cement.

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 20 1961  
CONSERVATION DIVISION  
Wichita, Kansas