

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

15-185-20866-0000
RECEIVED Form CP-4
STATE CORPORATION COMMISSION 12-15-80
9-7-82
SFP '7 1982

CONSERVATION DIVISION
Wichita, Kansas

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Stafford SEC. 9 TWP. 24 RGE. 12 E/W
Location as in quarters or footage from lines:
NE/NW/NW

Locate Well
correctly on above
Section Platt.

Lease Owner Warren American Oil Company
Lease Name Kelly Well No. #1-A
Office Address P. O. Box 971 - Midland, Texas 79701
Character of Well (Completed as Oil, Gas or Dry Hole): Gas
Date Well Completed _____
Application for plugging filed _____
Plugging commenced August 14, 1982
Plugging completed August 23, 1982
Reason for abandonment of well or producing formation Depleted

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well J. H. Metz
Producing formation _____ Depth to top _____ bottom T.D. 3900'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8"	287'	NONE
				4 1/2"	3899'	3380.44'

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Dumped sand to 3775' and four (4) sacks cement.
Shot pipe @ 3750' and 3500'.
Pulled one hundred two (102) joints of 4 1/2" casing.
Squeezed well with four (4) sacks hulls, twenty-five (25)
sacks cement, thirty (30) sacks gel, one (1) sack hulls ---
released plug --- one hundred twenty-five (125) sacks
50/50 pozmix cement with 4% added gel, and 3% calcium chloride.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rockhold Engineering, Inc.

STATE OF KANSAS COUNTY OF BARTON, ss.
James W. Rockhold (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) James W. Rockhold
JAMES W. ROCKHOLD - Box 698 - Great Bend,
(Address) Ks. 67530

SUBSCRIBED AND SWORN TO before me this 3rd day of Sept., 1982



Margaret Prosser
Notary Public.

My Commission expires _____

KANSAS DRILLERS LOG

COMPANY Warren American Oil Company

FARM Kelly "A" NO. 1

RECEIVED

NOV 20 1978 9 24S .12W C-NE NW NW

ROTARY TOTAL DEPTH 3,900'

COUNTY Stafford

COMM. November 6, 1978

COMP. November 14, 1978

CONTRACTOR H-30, Inc. (Rig #7)

ISSUED November 20, 1978

CASING

10 3/4"

8 5/8" Set at 287' cemented w/250 sxs cement

ELEVATION 1,882' K.B.

5 1/2"

4 1/2" Set at 3,899' cemented w/100 sxs cement

FIGURES INDICATE BOTTOM OF FORMATIONS

Sand and Shale	180'
Shale	295'
Shale and Shells	425'
Shale, Red Bed and Shells	675'
Anhydrite	695'
Shale and Shells	1,485'
Shale and Lime	1,740'
Lime and Shale	3,900'
Rotary Total Depth	3,900'


I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, Inc.

Dean Britting
Dean Britting

State of Kansas }
County of Sedgwick } ss:

Subscribed and Sworn to before me a Notary Public in and for said county and state this 20th day of November, 1978.



Elsie Willison
Elsie Willison - Notary Public

My Commission Expires:

July 25, 1982

RECEIVED
STATE CORPORATION COMMISSION
JUN 18 1982
CONSERVATION DIVISION
Wichita, Kansas