

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD

Reno County, Sec. 27 Twp. 24 Rge. 5 (W)

Location as "NE/CNW%SW%" or footage from lines SE NW SW

Lease Owner Drillers Production Co., Inc.

Lease Name C. Yoder Well No. 2

Office Address Ins. Bldg., 212 N. Mkt. St. Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Gas

Date well completed October 29 19 44

Application for plugging filed March 8 19 52

Application for plugging approved March 10 19 52

Plugging commenced Feb. 20 19 53

Plugging completed Feb. 24 19 53

Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production Feb. 29 19 52

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. Ruel Durkee

Producing formation Depth to top Bottom Total Depth of Well 3443 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Mississippi		3386		8 5/8" OD	503	None
				5 1/2" OD	3392	2212

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole w/ sand from 3443 to 3380 & ran 6 sacks cement. Shot & pulled 5 1/2 casing. Pumped 40 bbls oil behind pipe to loosen. Mudded hole to 310' set 10' rock bridge & ran 15 sacks cement at 300'. Mudded hole to 15' & ran 5 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor West Supply Co.

Address Chase, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

C. R. Bickford, Jr. (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *C. R. Bickford, Jr.*



Ins. Bldg., 212 N. Mkt. St. Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 4 day of March, 19 53.

Bertha L. Wilson

Notary Public.

My commission expires August 13, 1955



CONSERVATION DIVISION
Wichita, Kansas

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - DRILLERS GAS CO.
Farm - C.D.Yoder No. 2.

SEC. 27 T. 24 R. 5 W
S E NW SW

Total Depth. 3443'
Comm. 9-20-44 Comp. 10-29-44
Shot or Treated.
Contractor. Beardmore Drlg. Co.
Issued. 12-9-44

County. Reno
KANSAS



CASING:
8 5/8" 503'
5 1/2" 3392'

Elevation. _____

Production. 1,060,000 G.

Figures Indicate Bottom of Formations.

soil	10
shale	20
sand	80
shale & red rock	140
red rock	152
shale & shells	502
shale & lime	770
lime brkn	930
shale & lime	1045
sand	1065
shale & lime	1135
lime brkn	1315
shale & lime	1800
lime brkn	2200
lime	2405
shale & lime	2486
shale	2570
lime	2590
shale & lime	2730
lime	2950
shale	2975
lime	3380
shale	3388
chat	3443
Total Depth	

PLUGGING
FILE SEC-27-T-24-R-SW
PAGE 149 LINE 1

1052