

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH

Locate well correctly on above
Section Plat

RENO County. Sec. 27 Twp. 24S Rge. (E) 5 (W)

Location as "NE/CNW/SW" or footage from lines NE/SE NW

Lease Owner STELBAR OIL CORPORATION, INC.

Lease Name SCHROCK Well No. 1

Office Address 310 PETROLEUM BLDG., WICHITA, 2, KANSAS

Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE

Date well completed NOVEMBER 23, 1959

Application for plugging filed NOVEMBER 23, 1959

Application for plugging approved NOVEMBER 23, 1959

Plugging commenced NOVEMBER 23, 1959

Plugging completed NOVEMBER 23, 1959

Reason for abandonment of well or producing formation DRY HOLE

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well FRED W. HAMPEL

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3147 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

MUD TO 240', SET PLUG, DUMPED 15 SACKS CEMENT, MUD TO 30', SET PLUG, DUMPED 8 SACKS CEMENT, STEEL CAP WELDED ON SURFACE PIPE, TWO SACKS CEMENT IN RAT HOLE.

RECEIVED
STATE CORPORATION COMMISSION
12-14-59
DEC 14 1959
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor STELBAR OIL CORPORATION, INC.

Address 310 PETROLEUM BLDG., WICHITA, KANSAS

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
BERTRAND M. LESTER, JR. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bertrand M. Lester
310 PETROLEUM BLDG., WICHITA, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 11 day of DECEMBER, 19 59

My commission expires JAN. 18, 1960 Leon Ferguson Notary Public.



LOG

FARM: SCHROCK
WLL No. 1
NE SE NW
SECTION 27-24S-5W
RENO COUNTY, KANSAS

OWNER: STELBAR OIL CORPORATION, INC.
CONTRACTOR: STELBAR OIL CORP., INC.
DRILLING COMMENCED: 11-14-59
DRILLING COMPLETED: 11-23-59

8-5/8" 264' CEMENTED W/200 SACKS

ELEVATION: 1521 DF

0	30	SURFACE CLAY
30	75	SAND AND CLAY
75	2100	SHALE AND SHELLS
2100	2350	LIME
2350	2552	LIME AND SHALE
2552	2669	SANDY SHALE
2669	3147	KANSAS CITY LIME
	3147	TOTAL DEPTH, DRY AND ABANDONED