


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Reno County. Sec. 27 Twp 24N Rge. (E) 5 (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines C-SE-SE-NE
Lease Owner The Carter Oil Company
Lease Name D. E. Schrock Well No. 1
Office Address Box 786 - Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 1-16-53 19
Application for plugging filed 1-18-53 19
Application for plugging approved 1-19-53 19
Plugging commenced 1-19-53 19
Plugging completed 1-20-53 19
Reason for abandonment of well or producing formation Dry Hole



If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruef Durkee
Producing formation None Depth to top Bottom Total Depth of Well 3945 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Mississippi	Dry	3391	3426	10 3/4"	269'	
Morrow	Dry	3730'	3752			
Arbuckle	Dry	3924	3945'			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mud 3945' to 250'
Cement 250' to 210'
Mud 210' to 14'
Cement 14' to Base of cellar

Rec'd
3-5-53

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Prime Transit Corporation
Address Oklahoma City, Oklahoma

STATE OF Kansas, COUNTY OF Barton, ss.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God,

(Signature) W. Maxwell (Dist. Supt.)
Box 786- Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 3 day of March, 1953
My Commission Expires July 29, 1954
Notary Public.

PLUGGING
FILE SEC 27 T 24 R 534
BOOK PAGE 75 LINE 8

State

CARTER OIL COMPANY

D. E. SCHROCK #1

C SE SE NE Section 27-24S-5W

Date Comm. 12-26-52

Reno County, Kansas

Date Comp. 1-16-53

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Clay	0	35	
Sand	35	80	
Shale	80	245	
Shale and shells	260	420	
Salt	420	550	
Shale and shells	550	728	
Anhydrite	728	762	
Shale and lime	762	1060	
Lime and shale	1060	1475	
Shale and lime	1475	1795	
Lime and shale	1795	1860	
Shale and lime	1860	2090	
Lime and shale	2090	2300	
Lime	2300	2375	
Lime and Shale	2375	2520	
Sand	2520	2645	
Shale and lime	2645	2680	
Lime	2680	3035	
Lime and shale	3035	3270	
Shale	3270	3373	
Shale and chert	3373	3390	
Chert	3390	3396	
Lime and chert	3396	3411	
Chert	3411	3421	
Lime and chert	3421	3426	
Cherty Lime	3426	3450	
Lime and chert	3450	3510	
Chert and lime	3510	3540	
Lime and chert	3540	3585	
Cherty lime and shale	3585	3600	
Lime and shale	3600	3659	
Shale	3659	3730	
Shale and lime	3730	3752	
Lime and shale	3752	3815	
Sand	3815	3825	
Lime and sand	3825	3855	
Sandy shale and lime	3855	3925	
Sandy shale and lime	3855	3925	
Lime	3925	3944	
Total depth		3944	

PLUGGING
 FILE SEC 27-24-R-524
 BOOK PAGE 25 LINE 8

RECEIVED
 DIVISION
 1953
 DIVISION
 Kansas

I hereby certify the foregoing to be a true and accurate Driller's Log of the formations encountered in the above well.

PRIME DRILLING COMPANY

BY L. J. Kruse
L. J. Kruse

Subscribed and sworn to before me this 23rd day of January, 1953.
 commission expires Sept. 25, 1956

Betty Ben Garrison, Notary Public