


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Stafford County. Sec. 3 Twp. 24 Rge. 14 (E) W (W)
Location as "NE/CNW&SW" or footage from lines SE SE SE
Lease Owner Aylward Drilling Company
Lease Name Owen Well No. 1
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Gas
Date well completed September 1, 19 60
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 7-8-61 19
Plugging completed 7-16-61 19
Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4240 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	192'	None
				4-1/2"	4112'	2037'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole to 4092', ran sand to 3960' and dumped 5 sacks of cement @ 3960' with dump bailer. Pulled 4 1/2" casing. Bailed hole to 195', set rock bridge and ran 3 sacks of aquagel and 20 sacks of cement. Cement filled to 147'. Mudded from 147' to 40', set 10' rock bridge to 30' and ran 10 sacks of cement to top.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION
6-27-62
JUN 27 1962
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Knight Casing Pulling Company
Address Chase, Kansas

STATE OF Kansas XXXX COUNTY OF Rice, ss.
Noel J. Knight (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Noel J. Knight
Chase, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 20th day of July, 19 61

Milton J. Volin

My commission expires May 20, 1964

Notary Public.



BEN F. BRACK OIL COMPANY, INC.
309-10 BROWN BUILDING
WICHITA 2, KANSAS

ANNA BROWN #1

SE SE SE

Sec. 3-24S-14W

Stafford County, Kansas

Total Depth: 4240'
Elevation: 1957' DF
1954' Gr.

Spudded: 12-14-52
Rotary Commenced: 1-2-53
Rotary Completed: 1-19-53

WELL LOG

Spudded	0 -	195'
Red Sed - Shale		870
Anhydrite		890
Shale & Shells		1050
Shale & Lime		1080
Shale & Shells		1850
Lime & Shale		1720
Shale & Shells		1940
Lime & Shale		2130
Shale & Shells		2150
Lime & Shale		3620
Shale & Lime		3695
Lime		3966
Lime & Shale		3969
Shale & Chert		4102
Lime & Shale		4120
Lime & Chert		4147
Lime & Shale		4216
Lime		4240' T.D.
		D&A

FORMATIONS

Lansing	3640'
Conglomerate	3969'
Viola	4047
Simpson	4162
Arbuckle	4202

Above depths denote bottom of formations.

Casing Record

8 5/8"

192'

To the best of my knowledge, the above is a true and correct statement of the depths and formations and where found.

BEN F. BRACK OIL COMPANY, INC.

By

WITNESSED:

January 22, 1953

STATE CORP. COMMISSION

JAN 27 1953

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING

FILE SEC 3 T 2 L R 1424
BOOK PAGE 74 LINES 23