


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD



Locate well correctly on above
Section Plot

Stafford County. Sec. 3 Twp. 24 Rge. 14 (X) W (W)
Location as "NE/CNWSW" or footage from lines C NE/4 NE/4
Lease Owner JEREL, INC.
Lease Name SAYLER Well No. 1
Office Address Box 342, Great Bend, Kansas 67530
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed January 6 19 74
Application for plugging filed January 6 19 74
Application for plugging approved January 6 19 74
Plugging commenced January 6 19 74
Plugging completed January 6 19 74
Reason for abandonment of well or producing formation _____
If a producing well is abandoned, date of last production _____ 19 ____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well G. Russell Bieberstein
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4030 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Hole full of heavy mud to 500'. Plug set with 40 sacks cement thru drill pipe.
Middle plug set at 200' w/ 25 sacks cement thru drill pipe.
Top plug set at 40' w/ 1/2 sk. hulls and 15 sacks cement.
3 sacks cement in rat hole.

RECEIVED
STATE CORPORATION COMMISSION
JAN 11 1974
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor _____
Address _____

STATE OF KANSAS COUNTY OF Barton, ss.
Leonard Williamson (employee of owner) or (~~agent~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leonard Williamson
Box 823 - Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 10th day of 1 JANUARY, 19 74

My commission expires April 11, 1974

Harvey M. Hague
Notary Public.

WELL LOG

DATE COMMENCED: December 17, 1974
DATE COMPLETED: January 6, 1974

Jerel, Inc.
SAYLER #1
C NE/4 NE/4
Sec. 3-T24/R14W
Stafford County, Kansas

0 - 55' Surface Clay
55 - 160' Sand
160 - 250' Shale
250 - 350' Clay & Sand
350 - 874' Red Bed & Shale
874 - 896' Anhydrite
896 - 1698' Shale & Shells
1698 - 3468' Lime & Shale
3468 - 3471' Shale
3471 - 3612' Lime & Shale
3612 - 3630' Br. Lime
3630 - 3880' Lime
3880 - 3957' Lime & Shale
3957 - 4030' Lime, Shale, Chert, Sand
4030' RTD

ELEVATION: 1954 K.B.

FORMATION DATA

ANHYDRITE 874
HEEBNER 3468
BROWN LIME 3612
LANSING 3630
CONGLOMERATE 3957
RTD 4030

SURFACE PIPE: Set new
20# 8-58" pipe at 250'
with 185 sacks 60/40 poz-
mix, 2% Gel, 3% cc.

RECEIVED
STATE CORPORATION COMMISSION
JAN 11 1974
CONSERVATION DIVISION
TOPEKA, KANSAS

AFFIDAVIT

STATE OF KANSAS
COUNTY OF BARTON) ; ss

Leonard Williamson of lawful age does swear and state that the facts and
statements herein contained are true and correct to the best of his knowledge.

Leonard Williamson

Subscribed and sworn to before me this 10 day of January 1974.

My Comm. Expires:
April 11, 1974

Heather M. Hogue
Notary Public