

STATE OF KANSAS
STATE CORPORATION COMMISSION
Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH

Locate well correctly on above
Section Plat

Stafford County, Sec. 3 Twp. 24 Rge. 14 (W)
Location as "NE/CNW&SW&" or footage from lines SW SW NW
Lease Owner Welch & Olsson Drilling Co., Inc.
Lease Name Koelsch Well No. 1
Office Address 1017 Union Nat'l Bank Bldg.
Character of Well (completed as Oil, Gas or Dry Hole) D & A
Date well completed June 23 1953
Application for plugging filed June 23 1953
Application for plugging approved June 23 1953
Plugging commenced June 23 1953
Plugging completed June 23 1953
Reason for abandonment of well or producing formation D & A

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. M. A. Rives
Producing formation Depth to top Bottom Total Depth of Well 4254 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	200'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mudded up to 195' and set wooden plug at 195'. Cemented and displaced 20 sacks cement through drill pipe onto plug at 195'.
Mudded up to 40' and set second wooden plug. Filled hole to bottom of well cellar with 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
JUL 20 1953
CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor Welch & Olsson Drilling Co., Inc.
Address 1017 Union Nat'l Bank Bldg. - Wichita, Kansas

STATE OF KANSAS, COUNTY OF Sedgwick, ss.
R. E. Welch (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
1017 Union Nat'l Bank Bldg - Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 25th day of June 1953
[Signature] Notary Public.

My commission expires Feb 27-1956

PLUGGING
FILE SEC 3 T 24 R 14
BOOK PAGE 110 LINE 22

WELL LOG

WELCH & OLSSON DRILLING CO., INC.

Elevation: 1971 K.B.

Contractor: Welch & Olsson Drilling Co., Inc.

Commenced Drlg: 6-9-53

Koelsch No. 1

Completed Drlg: 6-23-53

SW SW NW Sec. 3-24S-14W

Stafford County, Kansas.

Production: D & A

Casing Record:

Set 200' of 8-5/8" with 175 sacks.

(Figures indicate bottom of formations)

<u>FORMATIONS</u>	<u>DEPTHS</u>	<u>FORMATION TOPS</u>
Surface Soil	25	Heebner 3488 -1517
Sand	160	Brown Lime 3629 -1658
Shale	225	Lansing 3646 -1675
Red Bed & Shale	905	Viola 4051 -2080
Anhydrite	921	Simpson 4165 -2194
Shale & Shells	1825	Arbuckle 4224 -2253
Lime & Shale	1950	
Lime	2025	
Lime & Shale	2090	
Shale & Shells	2590	
Sandy Lime	2605	
Lime & Shale	2735	
Shale & Shells	3115	
Lime & Shale	3190	
Lime with Shale Stks.	3270	
Lime	3505	
Shale	3575	
Heebner Shale	3629	
Lime	3635	
Shale	3643	
Lime	4000	
Cherty Lime	4051	
Simpson Shale	4165	
Shale	4225	
Lime	4254	

STATE OF KANSAS,)

(SS:-

SEDGWICK COUNTY,)

I hereby certify that the above is a true and correct copy of Drillers Log of well drilled in the SW SW NW of Section 3, Township 24 South, Range 14 West, Stafford County, Kansas.

RECEIVED
STATE CORPORATION COMMISSION
JUL 20 1953
T.D. CONSERVATION DIVISION
Wichita, Kansas

WELCH & OLSSON DRILLING COMPANY, INC.

BY: R. E. Welch

Subscribed and sworn to before me this 25th day of June, 1953.

My Commission Expires: Jul 27-1956

Marcella H. Davis
Notary Public

