

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Stafford

County. Sec. 22 Twp. 24S Rge. 12W (E) (W)

Location as "NE/CNW&SW&" or footage from lines SW SW NW

Lease Owner Rex & Morris Drilling Company

Lease Name Reid Well No. 1

Office Address P. O. Box 334 El Dorado, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) D&A

Date well completed 19 NOVEMBER 19 63

Application for plugging filed 26 DECEMBER 19 63

Application for plugging approved 27 DECEMBER 19 63


Plugging commenced 30 DECEMBER 19 63

Plugging completed January 3, 19 64

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Archie Elving

Producing formation NONE Depth to top Bottom Total Depth of Well 3956' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
SURFACE HOLE	WATER	SURFACE	243' RB	8 5/8"OD	237.51'	LEFT IN
VIOLA LIME	OIL & WATER	3905'	3956'	5 1/2"OD	3905'	3126'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

237' of 8 5/8" surface pipe, cemented with 180 sacks. 3905' of 5 1/2" long string, cemented with 100 sacks. Plug back to 3700'. Top perforations 3682', Bottom of hole sanded to 3670', and cemented with 5 sacks. Fluid was up in hole, and would not bail down. Plug was pushed to 250', 10' rock bridge. 6 sacks of cement was mixed in barrel and put on plug through dump bailer, and let set over night. Next morning hole bailed down and 20 sacks cement was added to plug. Hole was filled with mud to 40', 10' rock bridge, cemented with 10 sacks to base of cellar. 3126' of 5 1/2" long string was recovered from the hole.

RECEIVED
STATE CORPORATION COMMISSION
7-15-65
JUL 15 1965

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Comstock Pipe Pulling Inc.

Address Stafford, Kansas

STATE OF KANSAS, COUNTY OF BUTLER, ss.
A. H. FISHER (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) A. H. Fisher

P. O. BOX 334, EL DORADO, KANSAS

(Address)

SUBSCRIBED AND SWORN TO before me this 14TH day of JULY, 19 65

Hazel N. Dilts
HAZEL N. DILTS

Notary Public.

My commission expires 5 MAY 1969

Elevation 1880 RB
1877 DF

REID #1

Rex & Morris Drilling Company

Total Depth: 3956
Contractor: Rex & Morris
Commenced: 10-25-63
Completed: 1-3-64
Initial Prod.: D. & A.

Location: SW SW NW
Section 22-24S-12W
Stafford County, Kansas

Casing Record:
8 5/8 @ 243' w/130 sacks
5 1/2 @ 3905' w/100 sacks
(Pull 3126' pipe)

FORMATION	DEPTH
Surface Hole	243
Shale	1540
Shale and Lime	1705
Lime and Shale	2975
Lime	3270
Lime and Shale	3515
Lime	3776
Shale and Lime	3830
Shale	3900
Lime	3910

RECEIVED
STATE CORPORATION COMMISSION

JUL 15 1965

CONSERVATION DIVISION
Wichita, Kansas

TEST, DP and CO. Show oil and gas.
At 390' water, 10' oil, 12 hrs.

Lime TD 3956

Plug back 3700'. Perf. 3582-86. Test 6 gal.
water per hr. Acid 1000 gal. Swab down.
Final test 33.37 BW, 9 hrs., 7 BO and 26.37 BW.
Plug and abandoned.

I hereby certify the foregoing statements are true and correct to the best of my knowledge and belief.

Rex & Morris Drilling Company

By Paul D. Kountz
Paul D. Kountz, Geologist

STATE OF KANSAS
COUNTY OF BUTLER, SS.

Subscribed and sworn to before me, a Notary Public, this 7th day of January, 1964.

Elizabeth Deachner
Elizabeth Deachner, Notary Public

My commission expires: August 8, 1966