

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

STAFFORD County. Sec. 22 Twp. 24 Rge. 12W (E) (W)

Location as "NE/CNW/SW" or footage from lines: SW NE SW

Lease Owner: SANTA FE PIPE & SUPPLY

Lease Name: ERHART Well No. 2

Office Address: P. O. BOX 562 - GREAT BEND, KANSAS

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed: 19__

Application for plugging filed: JUNE 16 19 59

Application for plugging approved: JUNE 17 19 59

Plugging commenced: JUNE 15 19 59

Plugging completed: JUNE 23 19 59

Reason for abandonment of well or producing formation: DEPLETED

If a producing well is abandoned, date of last production: 19__

Was permission obtained from the Conservation Division or its agents before plugging was commenced?

Name of Conservation Agent who supervised plugging of this well: FRANK BROADFOOT

Producing formation: Depth to top: Bottom: Total Depth of Well: 4135' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	321'	none
				5 1/2"	4087'	3426'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet for each plug set.

SAND	4135'	-	4070'
CEMENT	4070'	-	4040'
MUD	4040'	-	300'
ROCK	300'	-	285'
CEMENT	285'	-	215'
MUD	215'	-	35'
ROCK	35'	-	30'
CEMENT	30'	-	0'

RECEIVED
STATE CORPORATION COMMISSION
JUL 20 1962
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor: GLENN & SMITH PIPE PULLING COMPANY

Address: P. O. BOX 114 - ELLINWOOD, KANSAS

STATE OF Kansas COUNTY OF Barton, ss.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]

P. O. Box - 562 - Great Bend, Kan. (Address)

SUBSCRIBED AND SWORN TO before me this 26 day of July, 19 62

My commission expires Jan. 26, 1963

Carmen Reinhardt Leiker Notary Public.



WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


COPY

Company: DEEP ROCK
Farm: Earhart "A" No. 2

SEC. 22 T. 24 R. 12W
ST NE SW

Total Depth. 4091'
Comm. 8-14-53 Comp. 8-30-53
Shot or Treated.
Contractor. Gabbert-Jones Drlg. Co.
Issued. 8-28-54

County Stanford
KANSAS



Elevation. 2001'

Production. Dry

CASING:

8 5/8" 321' cem w/225 sx
5 1/2" 4087' cem w/125 sx

Figures indicate Bottom of Formations.

clay	120
sand	150
shale & shells	325
shale & shells	965
anhydrite	995
shale & shells	1660
lime	1740
lime & shale	1958
lime	2425
lime & shale	2638
shale	3100
lime & shale	3145
lime	3829
lime & shale	3945
lime	3953
lime & chert	3969
shale & lime chert	3989
lime & chert	4056
lime & shale	4088
lime	4091
Total Depth	

Tops: Scout	
Heebner	3329
Brown Lime	3424
Lansing	3510
Viola	3935
Simpson	4042
Arbuckle	4084

RECEIVED
STATE CORPORATION COMMISSION

JUL 30 1962

CONSERVATION DIVISION
Wichita, Kansas