

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Stafford County. Sec. 23 Twp. 24 Rge. 12 (E) (W)

Location as "NE/CNW/SW" or footage from lines NW NE NE

Lease Owner Petroleum, Inc.

Lease Name Crawford 'A' Well No. 1

Office Address 305 East Third, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed November 3, 19 53

Application for plugging filed November 3, 19 53

Application for plugging approved November 3, 19 53

Plugging commenced November 3, 19 53


Plugging completed November 3, 19 53

Reason for abandonment of well or producing formation

Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Mr. M. A. Rives

Producing formation Depth to top Bottom Total Depth of Well 4055 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	233'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mudded up to 220' and set wooden plug at 220'. Placed 1/4 sacks hulls on top of plug at 220'. Cemented and displaced 20 sacks cement through drill pipe onto plug at 220'. Mudded up to 40' and set second wooden plug at 40'. Filled hole to bottom of well cellar with 10 sacks cement.

Rec'd 11-14-53

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Garvey Drilling Company

Address R.R. #2, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

W.W. Fisher (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) W.W. Fisher

305 East Third, Wichita, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 12th day of November, 1953

My commission expires October 13, 1954

[Signature] Notary Public.



DRILLER'S LOG CRAWFORD 'A' #1

Petroleum, Inc., Operator

Section 23, Twp. 24S, Rge. 12W

Garvey Drilling Company, Contractor

Location: NW NE NE

Drilling Commenced: October 20, 1953

County: Stafford County, Kansas

Drilling Completed: November 3, 1953

Production: D & A

Casing Records: 233' w/175 cas

R.T.D.: 4055'

Figures below indicate bottom of formations:

		<u>Tops</u>
170	Surface Sand	
680	Red Bed	
1600	Shale & Shells	Heebner: 3281 (-1423)
3500	Lime & Shale	Brown Lime: 3433 (-1575)
3768	Lime	Lansing: 3463 (-1605)
3882	Lime & Shale	Viola: 3879 (-2021)
4005	Chert	Simpson: 3980 (-2122)
4035	Shale	Arbuckle: 4035 (-2197)
4055	Lime	
4055	R.T.D.	

I hereby certify that this is a true and correct log of the above mentioned well.

PETROLEUM, INC.

By W. W. F. L.

STATE OF KANSAS)
) SS:
COUNTY OF SEDGWICK)

Subscribed to and sworn to before me, a Notary Public, in said County and State, this 12th day of November, 1954.

Charlotte Martin
Notary Public

RECEIVED
STATE OF KANSAS NOTARY COMMISSION
NOV 14 1954

My commission expires: October 13, 1954.

PLUGGING
FILE SEC 23 T 24 R 12W
BOOK PAGE 112 LINE 42