


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Stafford County. Sec. 24 Twp. 24 Rge. 12W ~~XX~~
Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines _____
SW SE SW
Lease Owner Rex & Morris Drilling Company
Lease Name Brensing Well No. 1
Office Address P.O. Box 334, El Dorado, Kansas 67042
Character of Well (Completed as Oil, Gas or Dry Hole) _____



Dry Hole
Date Well completed August 15, 1977
Application for plugging filed Verbal Application 19____
Application for plugging approved Verbal Approval 19____
Plugging commenced August 15, 1977
Plugging completed August 15, 1977
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production 19____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Bill Owens, Sr.
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3915'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

STATE CORPORATION COMMISSION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
AUG 25 1977 8-25-77 CONSERVATION DIVISION Wichita, Kansas				8-5/8"	324'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy rotary mud from 3915 ft. (rotary total depth) to 500 ft. Set plug at 500 ft. and cemented with 40 sacks cement. Filled hole with heavy rotary mud from 500 ft. to 300 ft. Set plug at 300 ft. and cemented with 35 sacks cement. Filled hole with heavy rotary mud from 300 ft. to 40 ft. Set solid plug at 40 ft. and cemented to cellar with 12 sacks cement, 3 sacks cement in rat hole.

Plugging operations accomplished utilizing Sun Oil Well Cementing pump truck through 4-1/2 inch drill pipe.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sun Oil Well Cementing, Inc.
Box 169, Great Bend, Kansas 67530


STATE OF Kansas COUNTY OF Sedgwick, ss.
Dean Britting, Agent (~~employee of owner~~ ~~owner or operator~~)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dean Britting
200 No. Main, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 23rd. day of August, 1977

Elsie Willison
Elsie Willison - Notary Public.
My commission expires June 30, 1978



KANSAS GEOLOGICAL SOCIETY API NO. - 15-185-20,761
 KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 508 EAST MURDOCK - WICHITA, KANSAS

COMPANY **Rex & Morris Drilling Company**


SEC. 24 T. 24S R. 12W
 LOC. SW SE SW

FARM **Brensing** NO. 1

TOTAL DEPTH **3915'**
 COMM. **August 8, 1977**
 SHOT OR TREATED
 CONTRACTOR **H-30, Inc.**
 ISSUED **August 23, 1977**

COMP. **August 15, 1977**

COUNTY **Stafford**
 KANSAS



CASING

20	10		
15	8	-5/8" 324' cemented w/235 axs cement	ELEVATION 1856 KB
12	6		
13	5		

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

Sand and Shale	327'
Red Bed and Shale	1,413'
Shale and Red Bed	1,770'
Shale and Lime	1,950'
Lime and Shale	3,915'
Rotary Total Depth	3,915'

RECEIVED
 STATE CORPORATION COMMISSION
 AUG 25 1977
 CONSERVATION DIVISION
 Wichita, Kansas

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

Dean Britting
 Dean Britting

State of Kansas }
 County of Sedgwick } ss:

Subscribed and Sworn to before me a Notary Public in and for said county and state this 23rd. day of August, 1977.

Elsie Willison
 Elsie Willison-Notary Public

My Commission Expires:
 June 30, 1978

