

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

FEB 6 1964
2-6-64

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Clinton Oil Co. & Navajo Drilling Co.

Complete Address: 6810 W. Highway 54, Wichita, Kansas

Lease Name Kissling Well No. # 1

Location SW NW SW Sec. 25 Twp. 24 Rge. 12 (E) (W) W

County Stafford Total Depth 4116

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Knight Casing Pulling Co.

Address: Box 304, Chase, Kansas License No. 436

Operation Completed: Hour 4:40PM Day 29th Month Jan. Year 1964

The Above well was plugged as follows:

There was supposed to be 240' of surface, but actually it was 174' of
8 5/8" surface pipe, cement circulated, 4116' of 5 1/2" long string, cement-
ed with 150. Plug back to 4080'. Top perforation 3821'. Bottom of hole
sanded to 3800', and cemented with 5 sacks. Fluid in hole was bailed down
to 200'. Plug was set at 200', with 10' rock bridge, and cemented with 25
sacks. Hole was filled with mud to 40', 10' rock bridge, and cemented
with 10 sacks to base cellar.

3003' of 5 1/2" long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 2/6/64
INV. NO. 8591-W