

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

MAY 17 1966
5-17-66
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Stickle Drilling Company

Complete Address: 1100 Bitting Bldg., Wichita, Kansas

Lease Name Jenkins Well No. # 1

Location C SE SW Sec. 35 Twp. 24 Rge. 12 (E) (W) W

County Stafford Total Depth 4160'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Stickle Drilling Company

Address: 1100 Bitting Bldg., Wichita, Kansas License No. _____

Operation Completed: Hour 12: PM Day 13th Month May Year 1966

The Above well was plugged as follows:

210' of 8 5/8" surface pipe, cemented with 200 sacks. Fluid level in
the hole was at 160'. 1st cementing plug and 1/2 sack of hulls was pushed
in fluid to 200', and cemented with 25 sacks, through the drill pipe.
Hole was filled with drilling mud to 40', 2nd cementing plug, bridged
solid with 1/2 sack of hulls on fluid at 40', and cemented with 10 sacks
to the base of the cellar. Rat hole bridged and cemented with 2 sacks.
This cementing was done by Halliburton Cementing Company

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 5/17/66
INV. NO. 3235-U

Signed: Archie Elving
Well Plugging Supervisor