

Form CP-3  
Rev. 6-26-62

W  
KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
12-2-63  
DEC 2 1963

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Dianne McCarthy

Complete Address: 407 Insurance Bldg., Wichita, Kansas

Lease Name Fritzemeyer Well No. # 1

Location SW SW NW Sec. 3 Twp. 24 Rge. 12 (E) (W) W

County Stafford Total Depth 3995

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: Gabbert-Jones Inc.

Address: 514 Orpheum Bldg., Wichita, Kansas License No.     

Operation Completed: Hour 10:00AM Day 28th Month Nov. Year 1963

The Above well was plugged as follows:

205' of 8 5/8" surface pipe, cemented with 210 sacks. Fluid was up in  
hole. 1st cementing plug and 1/4 sack hulls was pushed to 250', cemented  
with 30 sacks, through the drill pipe. Hole was filled with drilling  
mud to 40', 2nd cementing plug, bridged with 1/2 sack hulls, cemented  
with 10 sacks to base cellar. Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 12/3/63

INV. NO. 8216-W

Signed: Archie Elving  
Well Plugging Supervisor